


¹
²
The Long-Baseline Neutrino Facility (LBNF)
Far Site Conventional Facilities

³
Preliminary Design Report



⁴

⁵

October 8, 2015

1 **Contents**

2	Contents	i
3	List of Figures	ii
4	List of Tables	iii
5	1 Introduction	1
6	1.1 The Long-Baseline Neutrino Facility for DUNE	1
7	1.2 Strategy and Requirements	2
8	1.3 Introduction to the Far Site Conventional Facilities	3
9	1.4 The LBNF Far Site CF Preliminary Design Report	4
10	2 Project Management	5
11	2.1 Project Structure and Responsibilities	5
12	2.2 SDSTA and SURF	6
13	2.3 CERN	8
14	2.4 Coordination within LBNF	8
15	2.5 LBNF/DUNE Advisory and Coordinating Structures	9
16	2.5.1 International Advisory Council (IAC)	11
17	2.5.2 Resources Review Boards (RRB)	11
18	2.5.3 Fermilab, the Host Laboratory	12
19	2.5.4 DUNE Collaboration	13
20	2.5.5 Long-Baseline Neutrino Committee (LBNC)	13
21	2.5.6 Experiment-Facility Interface Group (EFIG)	13
22	3 Existing Site Conditions	15
23	3.1 Existing Site Conditions Evaluation	15
24	3.2 Evaluation of Geology and Existing Excavations	19
25	3.2.1 Geologic Setting	19
26	3.2.2 Rock Mass Characteristics: LBNF	19
27	3.2.3 Geologic Conclusions	21
28	References	23

List of Figures

1	1.1	Underground cavern layout	3
2	2.1	LBNF Work Breakdown Structure (WBS) to Level 3	6
3	2.2	LBNF Organization	7
4	2.3	Joint LBNF/DUNE management structure	10
5	3.1	Regional context showing the city of Lead, South Dakota	16
6	3.2	SURF Complex shown in the context of the city of Lead, South Dakota	17
7	3.3	LBNF core locations and geological features	21
8	3.4	Contour of stress safety factor	22
9			
10			

1 List of Tables

2

1 Todo list

2 add citation, doc 117	9
3 where are these defined?	12
4 beyond those identified in the (year) assessment of the existing facility conditions done for (this 5 needs some context)	15
6 ...who owned and operated the Homestake Mine on the site until (whatever year)? (this needs 7 context)	15
8 year	15
9 who is HDR?	18
10 citation	18
11 you evaluate for an assessment? Not clear what you want to say here. 'evaluated or assessed 12 with regard to these aspects'? 'given a preliminary evaluation to see if they're ready for an 13 assessment'? I'm confused (same comment next bullet)	18
14 cite	19
15 range of the?	20
16 citation	21

¹⁷ Chapter 1

¹⁸ Introduction

cf-intro

¹⁹ 1.1 The Long-Baseline Neutrino Facility for DUNE

- ¹ The global neutrino physics community is developing a multi-decade physics program to measure
² unknown parameters of the Standard Model of particle physics and search for new phenomena.
³ The program will be carried out as an international, leading-edge, dual-site experiment for neutrino
⁴ science and proton decay studies, which is known as the *Deep Underground Neutrino Experiment*
⁵ (*DUNE*), supported by the *Long-Baseline Neutrino Facility* (*LBNF*).

⁶ To achieve its ambitious physics objectives as a world-class facility, this program has been conceived
⁷ around three central components:

⁸ 1. an intense, wide-band neutrino beam

⁹ 2. a fine-grained near neutrino detector just downstream of the neutrino source

¹⁰ 3. a massive liquid argon time-projection chamber (LArTPC) deployed as a far neutrino detector
¹¹ deep underground, 1,300 km downstream; this distance between the neutrino source and far
¹² detector – the *baseline* – is measured along the line of travel through the Earth

¹³ The neutrino beam and near detector will be installed at the Fermi National Accelerator Laboratory
¹⁴ (Fermilab), in Batavia, Illinois. The far detector will be installed at the Sanford Underground
¹⁵ Research Facility (SURF) in Lead, South Dakota. The experiment’s detectors at the two sites will
¹⁶ be designed, built, commissioned and operated by the international DUNE Collaboration. LBNF
¹⁷ is the facility designed to support the experiment. LBNF will comprise

¹⁸ • the world’s highest-intensity neutrino beam at Fermilab

¹⁹ • a set of underground caverns to house the DUNE far detector modules at SURF

²⁰ • a beamline measurement system at the near site

- 21 • conventional facilities at both the near and far sites
- 22 • cryogenics infrastructure to support the DUNE detector at the far site
- 23 LBNF is hosted by Fermilab and its design and construction is organized as a DOE/Fermilab
1 project incorporating international partners.

2 1.2 Strategy and Requirements

3 The strategy for executing the scientific program was presented in the LBNF/DUNE Conceptual
4 Design Report (CDR)^{cd-r-cdr}[1]. The program has been developed to meet the requirements set out in the
5 P5 report^{p5-report-2014}[2] and takes into account the recommendations of the European Strategy for Particle
6 Physics^{euro-strat-2013}[3]. It adopts a model in which U.S. and international funding agencies share costs on
7 the DUNE detectors, and the European Organization for Nuclear Research (CERN) and other
8 participants provide in-kind contributions to the supporting infrastructure of LBNF. LBNF and
9 DUNE will be tightly coordinated as DUNE collaborators design the detectors and infrastructure
10 that will carry out the scientific program.

11 The requirements on LBNF derive from the DUNE Collaboration science requirements^{dune-sci-req}[4], which
12 drive the space and functional needs of the far detector construction and operation, and from
13 Environment, Safety and Health (ES&H) and facility operations requirements. The LBNF and
14 DUNE requirements are maintained together in^{dune-sci-req}[4]. Conventional Facility requirements are detailed
15 in the Arup 100% Preliminary Design Report^{arup:fsci100pdr}[5].

16 The DUNE far detector is designed as a set of four 10-kt fiducial mass modules. The caverns and
17 the services to the caverns will be as similar to one another as possible in order to implement
18 efficiency in design, construction and operation. Figure 1.1 shows the layout of the underground
19 caverns that will house the detector modules, and the separate cavern that will house utilities and
20 cryogenics systems.

21 While the SURF site already meets many of the requirements from the geological, scientific and
22 engineering standpoints, significant work is required to provide the space and infrastructure for
23 the experiment's installation and operation.

24 This PDR presents the scope of the LBNF Far Site Conventional Facilities (FSCF) at SURF, the
25 present and future states of the site, evaluation and assessment of its facilities and the provisioning
26 of associated infrastructure such as power, water, plumbing, ventilation, etc. Also described are
27 the tasks and processes planned for developing the surface and underground structures and the
28 requisite safety measures.




Figure 1.1: Underground cavern layout (SRK, Courtesy SURF)

fig:unde

1.3 Introduction to the Far Site Conventional Facilities

The scope of the FSCF includes design and construction for facilities on the surface and underground at SURF for DUNE.

The primary element of the Far Site Conventional Facilities (FSCF) is the set of underground spaces required to install, operate and support the multi-module cryogenic DUNE far detector. The underground conventional facilities include new excavated spaces at the 4850L for the detector modules, utility spaces for experiment equipment, utility spaces for facility equipment, drifts for access, and spaces required for construction. Underground infrastructure that FSCF must provide for DUNE includes power to experiment equipment, cooling systems for that equipment and cyberinfrastructure for data collection. Underground infrastructure required for the facility includes domestic (potable) water, industrial water for process use and fire suppression, fire detection and alarm systems, normal and standby power systems, a sump-pump drainage system for native and leak water around the detector, water drainage to the facility-wide pump discharge system, and cyberinfrastructure for communications and security. In addition to providing new spaces and infrastructure underground, FSCF enlarges some existing spaces for use, such as the access drifts from the Ross Shaft to the new caverns, and provides infrastructure for these spaces. New piping is provided in the shaft for cryogens (gas argon transfer line and nitrogen compressor suction and discharge lines) and water as well as for power cables and cyberinfrastructure.

Many buildings and utilities exist above-ground at SURF, some of which will be utilized for LBNF. The scope of the surface FSCF includes only that work necessary for LBNF; it does not include the general rehabilitation of buildings on the site, which remains the responsibility of SURF. Electrical substations and distribution will be upgraded to increase power and provide standby capability for life safety. An existing building will be remodeled to house both office space and an experiment/facility control room, and a new building will be constructed near the existing Ross Shaft to support cryogen transfer from the surface to the 4850L. To reduce the risk of failure of aging

23 but essential support equipment during the construction and installation periods, several SURF
24 infrastructure-reliability activities are included in the earlier phases of the LBNF Project. These
25 include completion of the Ross Shaft rehabilitation, rebuilding of hoist motors, and replacement
1 of the Oro Hondo fan. Failure of any of this aging infrastructure could limit or stop access to the
2 underground.

3 1.4 The LBNF Far Site CF Preliminary Design Report

4 The *LBNF Far Site Conventional Facilities Preliminary Design Report* describes the preliminary
5 designs for the conventional facilities planned for the Sanford Underground Research Facility
6 (SURF), the LBNF Far Site. This document is an evolution of *LBNF/DUNE CDR Annex 3C:*
7 *Conventional Facilities (CF) at the Far Site*, which was prepared for the LBNF/DUNE CD-1-
8 Refresh Review in July 2015. The original LBNF/DUNE Conceptual Design Report volumes
9 have been updated [6, 7, 8, 9] as required to provide context for the LBNF Far Site Conventional
10 Facilities design.

11 The scope of this Preliminary Design Report (PDR) is limited to the LBNF Far Site Conventional
12 Facilities (FSCF); the cryogenics infrastructure is not included.

- 13 1. This chapter provides a short introduction to LBNF, DUNE and the FSCF.
- 14 2. Chapter 2 ^[ch:intro-pm] summarizes the management structure for LBNF.
- 15 3. Chapter 3 ^[ch:fscf-site-cond] describes the existing site conditions at SURF.
- 16 4. Chapter ?? ^[ch:fscf-surf-facil] describes the existing and planned surface buildings that will support the DUNE
17 far detector, planned for installation at the 4850L of SURF.
- 18 5. Chapter ?? ^[ch:fscf-excav] discusses the planned underground excavation.
- 19 6. Chapter ?? ^[ch:fscf-und-infra] describes the underground infrastructure necessary to facilitate installation and
20 operation of the DUNE far detector modules.
- 21 7. Chapter ?? ^[ch:fscf-siteprep] describes the restoration and maintenance activities required at the SURF site
22 that are included in the overall LBNF Project and planned to be executed as early Site
23 Preparation.

24 This PDR is supported by a Design Report from the independent engineering firm, Arup, USA[5]. ^[arup:fscf100pd]

²⁵ Chapter 2

²⁶ Project Management

intro-pm

²⁷ 2.1 Project Structure and Responsibilities

¹ The LBNF Project is charged by Fermilab and DOE to design and construct conventional and technical facilities needed to support the DUNE Collaboration. LBNF is organized as a DOE/Fermilab project incorporating in-kind contributions from international partners. At this time, the major international partner is CERN, the European Organization for Nuclear Research. LBNF works closely with DUNE through several coordinating groups to ensure scientific direction and coordination for executing the LBNF Project such that the requirements of the program are met.

⁷ LBNF works closely with SURF management to coordinate design and construction for the far site conventional facilities for the DUNE far detector. CERN is providing cryogenics equipment and engineering as part of the cryogenics infrastructure at SURF. The design and construction of LBNF is supported by other laboratories and consultants/contractors that provide scientific, engineering, and technical expertise. A full description of LBNF Project Management is contained in the LBNF/DUNE Project Management Plan^[?].

¹³ LBNF coordinates with DUNE through regular technical team interactions between the two Projects as well as more formally through the Joint Management Team where day-to-day management coordination occurs, and the Experiment-Facility Interface Group, where major issues regarding interfaces and items affecting both Projects are discussed. In addition, the Projects share common Project Office staff and systems, and include a single, integrated project resource-loaded schedule and configuration management system.

¹⁹ LBNF consists of two major L2 subprojects, Far Site Facilities and Near Site Facilities, coordinated through a central Project Office located at Fermilab. Each L2 Project consists of two large L3 subprojects corresponding to the conventional and technical facilities, respectively, at each site. The project organizational structure, which includes leadership from major partners, is shown in Figure ??.

²⁴ The LBNF Project team consists of members from Fermilab, CERN, South Dakota Science and

Technology Authority (SDSTA), and Brookhaven National Laboratory (BNL). The team, including members of the Project Office as well as the L2 and L3 managers for the individual subprojects, is assembled by the Project Director. The Project team is shown in Figure 2.2. Line management for environment, safety and health, and quality assurance flows through the Project Director.

Through their delegated authority and in consultation with major stakeholders, the L2 Project Managers determine which of their lower-tier managers will be Control Account Managers (CAMs) for the Project WBS. L2 and L3 Project Managers are directly responsible for generating and maintaining the cost estimate, schedule, and resource requirements for their subprojects and for meeting the goals of their subprojects within the accepted baseline cost and schedule.




Figure 2.1: LBNF Work Breakdown Structure (WBS) to Level 3 (L3)

2.2 SDSTA and SURF

LBNF plans to construct facilities at SURF to house and support the DUNE far detector. SURF is owned by the state of South Dakota and managed by the SDSTA.




Figure 2.2: LBNF Organization

fig:lbnf

10 Current SURF activities include operations necessary for allowing safe access to the 4850L of the
11 former mine, which houses the existing and under-development science experiments. The DOE
12 is presently funding SDSTA ongoing operations through Lawrence Berkeley National Laboratory
1 (LBNL) and its SURF Operations Office through FY16; starting in FY17 it is expected that this
2 will change, and that funding will flow through Fermilab.

3 The LBNF Far Site Facilities Manager is also an employee of SDSTA and is contracted to Fer-
4 milab to provide management and coordination of the Far Site Conventional Facilities (CF) and
5 Cryogenics Infrastructure subprojects. LBNF contracts directly with SDSTA for the design of the
6 required CF at SURF; whereas the actual construction of the CF will be directly contracted from
7 Fermilab. Coordination between SDSTA and the LBNF Project is necessary to ensure efficient
8 operations at SURF. This will be facilitated via an agreement between SDSTA and Fermilab (not
9 yet available) that defines responsibilities and methods for working jointly on LBNF Project design
10 and construction. A separate agreement will be written for LBNF Operations.

11 **2.3 CERN**

12 The European Organization for Nuclear Research (CERN) is expected to significantly contribute
13 to LBNF with technical components that are required to support the deployment of both the
14 DUNE detectors and the neutrino beamline.

15 **2.4 Coordination within LBNF**

16 The LBNF Project organization is headed by the LBNF Project Director, who is also the Fermilab
17 Deputy Director for LBNF; this person reports directly to the Fermilab Director.

18 Within FermilabâŽs organization, the LBNF organization includes two new divisions – Far-Site
19 Facilities and Near-Site Facilities – as well as a project office, all led by the LBNF Project Director.
20 They have been created to execute the Far Site Facilities and Near Site Facilities subprojects. The
21 heads of these divisions report to the LBNF Project Manager. Any personnel working more than
22 half-time on these subprojects would typically be expected to become a member of one of these
23 divisions, while other contributors will likely be matrixed into part-time roles from other Fermilab
24 Divisions. The heads of the other Fermilab Divisions work with the L2 and L3 project managers
25 to supply the needed resources on an annual basis.

26 The LBNF WBS defines the scope of work. All changes to the WBS must be approved by the
27 LBNF Project Manager prior to implementation. The current WBS is shown in Figure 2.1. For
28 work on specific tasks required for the LBNF Project at the SURF site, SDSTA assigns engineers
29 and others as required. This is listed in the resource-loaded schedule as contracted work from
30 Fermilab for Far Site CF activities. CERN and Fermilab are developing a common cryogenics
31 team to design and produce the Cryogenics Infrastructure subproject deliverables for the far site.
32 CERN provides engineers and other staff as needed to complete their agreed-upon deliverables.

³³ LBNF has formed several management groups with responsibilities as described below. More detail
³⁴ is provided in the PMP

³⁵ add citation, doc 117

¹ .
² LBNF uses a *Project Management Board* to provide formal advice to the Project Director on
³ matters of importance to the LBNF Project as a whole. Such matters include (but are not limited
⁴ to) those that

- ⁵ • have significant technical, cost, or schedule impact on the Project
- ⁶ • have impacts on more than one L2 subproject
- ⁷ • affect the management systems for the Project
- ⁸ • have impacts on or result from changes to other Projects on which LBNF is dependent
- ⁹ • result from external reviews or reviews called by the Project Director

¹⁰ The Project Management Board serves as the

- ¹¹ • LBNF Change Control Board, as described in the Configuration Management Plan^[?] [CMP-10760]
- ¹² • Risk Management Board, as described in the Fermilab Risk Management Procedure for
¹³ Projects ^[?] [fnpl-risk-mgmt]

¹⁴ The Far Site CF (FSCF) Project has engaged three international experts in hard-rock underground
¹⁵ construction to advise it periodically through the design and construction process regarding ex-
¹⁶ cavation at SURF. This team, the FSCF *Neutrino Cavity Advisory Board (NCAB)*, meets at
¹⁷ the request of the FSCF-PM, generally on-site, to discuss specific technical issues. The NCAB
¹⁸ produces a report with its findings and conclusions for Project information and action.

¹⁹ 2.5 LBNF/DUNE Advisory and Coordinating Structures

²⁰ A set of structures has been established to provide coordination among the participating funding
²¹ agencies, oversight of the LBNF and DUNE projects, and coordination and communication between
²² the two projects. These structures and the relationships among them are shown in Figure 2.3 and
²³ are described in this section. [fig:lbnfdune-org]




Figure 2.3: Joint LBNF/DUNE management structure

fig:lbnf

24 2.5.1 International Advisory Council (IAC)

25 The International Advisory Council (IAC) is composed of regional representatives, such as CERN,
26 and representatives of funding agencies that make major contributions to LBNF infrastructure or
1 to DUNE. The IAC acts as the highest-level international advisory body to the U.S. DOE and
2 the FNAL Directorate, and facilitates high-level global coordination across the entire enterprise
3 (LBNF and DUNE). The IAC is chaired by the DOE Office of Science Associate Director for High
4 Energy Physics and includes the FNAL Director in its membership. The council meets as needed
5 and provides pertinent advice to LBNF and DUNE through the Fermilab Director.

6 Specific responsibilities of the IAC include, but are not limited to, the following:

- 7 • During the formative stages of LBNF and DUNE the IAC helps to coordinate the sharing
8 of responsibilities among the agencies for the construction of LBNF and DUNE. Individual
9 agency responsibilities for LBNF will be established in bilateral international agreements with
10 the DOE. Agency contributions to DUNE will be formalized through separate agreements.
- 11 • The IAC assists in resolving issues, especially those that cannot be resolved at the Resources
12 Review Boards (RRB) level, e.g., issues that require substantial redistributions of responsi-
13 bilities among the funding agencies.
- 14 • The IAC assists as needed in the coordination, synthesis and evaluation of input from Project
15 reports charged by individual funding agencies, LBNF and DUNE Project management,
16 and/or the IAC itself, leading to recommendations for action by the managing bodies.

17 The DUNE Co-Spokespersons and/or other participants within the Fermilab neutrino program
18 will be invited to sessions of the IAC as needed. Council membership may increase as additional
19 funding agencies from

20 2.5.2 Resources Review Boards (RRB)

21 The Resources Review Boards (RRB) are composed of representatives from all funding agencies
22 that sponsor LBNF and DUNE, and from the Fermilab management. The RRB provides focused
23 monitoring and detailed oversight of each of the Projects. The Fermilab Director in coordination
24 with the DUNE RC defines its membership. A representative from the Fermilab Directorate chairs
25 the boards and organizes regular meetings to ensure the flow of resources needed for the smooth
26 progress of the enterprise and for its successful completion.

27 The managements of the DUNE Collaboration and the LBNF Project participate in the RRB
28 meetings and make regular reports to the RRB on technical, managerial, financial and administra-
29 tive matters, as well as on status and progress of the DUNE Collaboration. DUNE Finance Board
30 members who serve as National Contacts from the sponsoring funding agencies will be invited to
31 RRB sessions.

32 Two groups exist within the RRB: RRB-LBNF and RRB-DUNE. Each of these groups monitors
33 progress and addresses the issues specific to its area while the whole RRB deals with matters that
34 concern the entire enterprise. The RRB meet biannually; these meetings start with a plenary
1 opening session and are followed by RRB-LBNF and RRB-DUNE sessions. As DUNE progresses
2 toward experimental operations, RRB-Computing sessions will convene.

3 The RRB employs standing DUNE and LBNF *Scrutiny Groups* as needed to assist in its responsi-
4 bilities. The scrutiny groups operate under the RRB, and provide detailed information on financial
5 and personnel resources, costing, and other elements under the purview of the RRB.

6 Responsibilities of the RRB include

- 7 • assisting the DOE and the FNAL Directorate, with coordinating and developing any required
8 international agreements between partners
- 9 • monitoring and overseeing the Common Projects and the use of the Common Funds

10 where are these defined?

- 11 • monitoring and overseeing general financial and personnel support
- 12 • assisting the DOE and the FNAL Directorate with resolving issues that may require reallo-
13 cation of responsibilities among the Project's funding agencies
- 14 • reaching consensus on a maintenance and operation procedure, and monitoring its function
- 15 • approving the annual Common Fund budget of DUNE for construction and for maintenance
16 and operation

17 **2.5.3 Fermilab, the Host Laboratory**

18 As the host laboratory, Fermilab has a direct responsibility for the design, construction, commis-
19 sioning and operation of the facilities and infrastructure (i.e., LBNF) that support the science
20 program. In this capacity, Fermilab reports directly to the DOE through the Fermilab Site Office
21 (FSO). Fermilab also has an important oversight role for the DUNE Project itself as well as an
22 important coordination role in ensuring that interfaces between the two Projects are completely
23 understood.

24 Fermilab's oversight of the DUNE Collaboration and detector construction project is carried out
25 through

- 26 • regular meetings with the Collaboration leadership
- 27 • approving the selection of Collaboration spokespersons

- 28 • providing the Technical and Resource Coordinators
- 29 • convening and chairing the Resources Review Boards
- 30 • regular scientific reviews by the Physics Advisory Committee (PAC) and Long-Baseline Neu-
1 trino Committee (LBNC)
- 2 • Director's Reviews of specific management, technical, cost and schedule aspects of the de-
3 tector construction project
- 4 • other reviews as needed

5 **2.5.4 DUNE Collaboration**

6 The Collaboration, in consultation with the Fermilab Director, is responsible for forming the
7 international DUNE Project team responsible for designing and constructing the detectors. The
8 Technical Coordinator (TC) and Resource Coordinator (RC) serve as the lead managers of this
9 international project team and are selected jointly by the spokespersons and the Fermilab Director.
10 Because the international DUNE Project incorporates contributions from a number of different
11 funding agencies, it is responsible for satisfying individual tracking and reporting requirements
12 associated with the different contributions.

13 **2.5.5 Long-Baseline Neutrino Committee (LBNC)**

14 The Long-Baseline Neutrino Committee (LBNC), composed of internationally prominent scientists
15 with relevant expertise, provides external scientific peer review for LBNF and DUNE regularly.
16 The LBNC reviews the scientific, technical and managerial decisions and preparations for the
17 neutrino program. It acts in effect as an adjunct to the Fermilab Physics Advisory Committee
18 (PAC), meeting on a more frequent basis than the PAC. The LBNC may employ DUNE and LBNF
19 Scrutiny Groups for more detailed reports and evaluations. The LBNC members are appointed by
20 the Fermilab Director.

21 **2.5.6 Experiment-Facility Interface Group (EFIG)**

22 Close and continuous coordination between DUNE and LBNF is required to ensure the success
23 of the combined enterprise. An Experiment-Facility Interface Group (EFIG) was established in
24 January 2015 to oversee and ensure the required coordination both during the design/construction
25 and operational phases of the program. This group covers areas including:

- 26 • interface between the near and far detectors and the corresponding conventional facilities

- 27 ● interface between the detector systems provided by DUNE and the technical infrastructure
28 provided by LBNF
- 29 ● design and operation of the LBNF neutrino beamline

1 The EFIG is chaired by the two deputy directors of Fermilab. Its membership includes the LBNF
2 Project Director and Project Manager, and the DUNE Co-Spokespersons, Technical Coordinator,
3 Resource Coordinator and the CERN-LBNF Project Manager. In consultation with the DUNE
4 and LBNF management, the EFIG Chairs will extend the membership as needed to carry out the
5 coordination function. In addition, the DOE Federal Project Director for LBNF, the Fermilab
6 Chief Project Officer, and a designated representative of the SDSTA will serve ex officio. The
7 EFIG Chairs designate a Secretary of the EFIG, who keeps minutes of the meetings and performs
8 other tasks as requested by the Chair.

9 It is the responsibility of the EFIG Chairs to report EFIG proceedings to the Fermilab Director and
10 other stakeholders. It is the responsibility of the DUNE spokespersons to report EFIG proceedings
11 to the rest of the Collaboration. The EFIG meets weekly or as needed.

¹² Chapter 3

¹³ Existing Site Conditions

¹⁴ The SDSTA currently operates and maintains the Sanford Underground Research Facility (SURF)
¹ at the former Homestake mine in Lead, South Dakota. The SURF property comprises 186 acres
² on the surface and 7,700 acres underground. The SURF Surface Campus includes approximately
³ 253,000 gross square feet (gsf) of existing structures. Using a combination of private funds through
⁴ T. Denny Sanford, South Dakota Legislature-appropriated funding, and a federal Department of
⁵ Housing and Urban Development (HUD) Grant, the SDSTA has made significant progress in
⁶ stabilizing and rehabilitating the SURF facility to provide for safe access and prepare the site for
⁷ new laboratory construction. These efforts have included dewatering of the underground facility
⁸ and mitigating and reducing risks

⁹ beyond those identified in the (year) assessment of the existing facility conditions done for
(this needs some context)

¹⁰ the former Deep Underground Science and Engineering Laboratory (DUSEL).

¹¹ Figure 3.1 shows SURF's location within the region as a part of the northern Black Hills of South
Dakota. Figure 3.2 outlines the SURF site in relationship to the city of Lead, South Dakota, and
¹³ points out various significant features of Lead including the surrounding property that still remains
¹⁴ under the ownership of Barrick Gold Corporation.

¹⁵ ...who owned and operated the Homestake Mine on the site until (whatever year)? (this needs
context)

¹⁶ 3.1 Existing Site Conditions Evaluation

¹⁷ The facility conditions as of




Figure 3.1: Regional context showing the city of Lead, South Dakota. (Dangermond Keane Architecture, Courtesy SURF)

fig:regi




Figure 3.2: SURF Complex shown in the context of the city of Lead, South Dakota, and the property remaining under ownership of Barrick. Area shown in yellow is a potential future expansion of the SDSTA property. [Dangermond Keane Architecture, Courtesy of SURF]

fig:surf

18 year

19 were assessed by HDR

20 who is HDR?

1 as part of the DUSEL Preliminary Design to evaluate the condition of existing facilities and
2 structures on the Yates, and Ross Campuses. They are documented in the DUSEL PDR, Section
3 5.2.4, [10]

4 citation

5 . The portions of DUSEL's assessment pertinent to the LBNF Project are included here; they
6 have been edited to reflect current activities and conditions. References to the DUSEL Project are
7 from that time, and are now considered historic.

8 The HDR assessments reviewed the condition of buildings that were proposed for continued use
9 in their then-current function, new use, or potential demolition. Assessments for buildings were
10 performed on their architectural, structural, mechanical/electrical/plumbing (MEP), civil, envi-
11 ronmental, and historic aspects. Site assessments looked at civil, landscape, environmental, and
12 historic aspects. Facility-wide utilities such as electrical, steam distribution lines, water and sewer
13 systems were also assessed. In particular:

- 14 • Buildings proposed for reuse were evaluated for preliminary architectural and full structural,
15 environmental, and historic assessments.

16 you evaluate for an assessment? Not clear what you want to say here. 'evaluated or as-
sessed with regard to these aspects'? 'given a preliminary evaluation to see if they're
ready for an assessment'? I'm confused (same comment next bullet)

- 17 • Buildings proposed for demolition were evaluated for preliminary historic assessments.

- 18 • Preliminary MEP assessments were performed on the Ross Substation, #5 Shaft fan, Oro
19 Hondo fan, Oro Hondo substation, and on the general site utilities for the Ross, Yates, and
20 Ellison Campuses.

- 21 • The waste water treatment plant (WWTP) received preliminary architectural and structural
22 assessments and a full MEP assessment.

- 23 • Preliminary civil assessments of the Kirk Portal site and Kirk to Ross access road were also
24 completed.

25 The assessment was completed in three phases and the detailed reports are included in the appen-
26 dices of the DUSEL PDR as:

- 27 ● Phase I Report, Site Assessment for Surface Facilities and Campus Infrastructure to Support
28 Laboratory Construction and Operations (DUSEL PDR Appendix 5.E)
- 29 ● Phase II Site and Surface Facility Assessment Project Report (DUSEL PDR Appendix 5.F)
- 1 ● Phase II Roof Framing Assessment (DUSEL PDR Appendix 5.G)

2 **3.2 Evaluation of Geology and Existing Excavations**

3 The accessible underground mine workings at SURF within the footprint of the former Homestake
4 Gold Mine are extensive. Over the life of the gold mine, over 360 miles of drifts (tunnels) were
5 mined, and shafts and winzes were sunk to gain access to depths in excess of 8,000 feet. A number
6 of underground workings are being refurbished by SURF, and new experiments are being installed
7 at the 4850L, the same level as proposed for the LBNF underground facilities. Geotechnical
8 investigations and initial geotechnical analyses were completed by Arup, USA

9 cite

10 for the DUSEL Preliminary Design and are described in detail in the DUSEL PDR. Additional
11 geotechnical investigation and analyses were performed, also by Arup, in 2014 specific to LBNF.
12 This section provides summaries of these two efforts, including work completed for DUSEL that is
13 applicable to LBNF (the text is excerpted from the DUSEL Preliminary Design Report, Chapter 5
14 Section 3). Much of the work completed for the alternative detector technology considered during
15 the DUSEL timeframe, a water Cherenkov detector (WCD), is also applicable to the current LBNF
16 design at the 4850L.

17 **3.2.1 Geologic Setting**

18 SURF is sited within a metamorphic complex containing the Poorman, Homestake, Ellison and
19 Northwestern Formations (oldest to youngest), which are sedimentary and volcanic in origin. An
20 amphibolite unit (Yates Member) is present within the lower known portions of the Poorman
21 Formation. The LBNF caverns have been located in the Poorman formation to isolate them from
22 the remainder of the level. The layout adopted on the 4850L attempts to optimize the needs for
23 ventilation isolation, access control, and orientation relative to the beamline.

24 **3.2.2 Rock Mass Characteristics: LBNF**

25 Following a similar strategy as DUSEL, LBNF initiated a second geotechnical program in 2013 to
26 evaluate the specific location under consideration and evaluate its appropriateness for the proposed
27 design. This was undertaken in two phases. The first phase was a mapping of the existing spaces

28 surrounding the proposed rock mass using both visual techniques and laser scanning to understand
29 the rock mass and to inform the scope of the second phase. The second phase included drilling
30 of four HQ (2.5-in diameter) core holes ranging in length from 477 to 801 feet as well as two 6-in
1 diameter core holes ~30 ft each. The smaller diameter cores were then evaluated for the following
2 characteristics:

- 3 • core recovery percent
4 • rock quality designation (RQD) percent
5 • rock type, including color, texture, degree of weathering, and strength
6 • mineralogy and presence of magnetic sulfides
7 • character of discontinuities, joint spacing, orientation, aperture
8 • roughness, alteration, and infill (if applicable)

9 Representative samples were selected from the overall core to test material strength and chemi-
10 cal characteristics. The [fig:core-loc](#) geotechnical site investigations area on the 4850L, showing boreholes is
11 presented in Figure 3.3.

12 The holes from which the smaller diameter core was removed were studied in several ways. An
13 absolute survey was conducted to allow the core holes to be plotted relative to cavern designs. An
14 optical televiewer was passed through each small hole to visualize the rock mass. This technique
15 allows visualization of foliation, joint openings, healed joints, and geological contact between rock
16 types. An acoustical imaging device was also used in one hole to complement the optical informa-
17 tion. The permeability of the rock was tested by pressurizing the small holes at various intervals to
18 determine whether joints allowed for the flow of water outside of the holes (hydraulic conductivity).
19 In all cases, the hydraulic conductivity was well below what can be accomplished using manmade
20 techniques such as grouting. Two of the small holes were plugged and instrumented to determine
21 whether water would flow into the holes over time. This test found very low flow rates (.0013 –
22 .0087 gpm). Ongoing evaluation of pressure build in these holes was inconclusive, as blast-induced
23 fracturing near the existing drifts allow the holes to depressurize outside of the

24 range of the?

25 test instruments.

26 The larger (6-in) diameter cores and holes were used for strength and stress testing. In situ stress
27 was tested by drilling a smaller diameter hole first, then gluing a strain gauge at 30 – 36 feet within
28 the depth. As the larger diameter core was removed, this strain gauge recorded the relaxation of the
29 rock. The removed core was re-drilled to provide smaller diameter samples at specific orientations
30 for strength testing, as the strength of the material varies based on applied force direction relative
31 to the foliation of the rock. These samples were also tested for time-dependent movement.




Figure 3.3: LBNF core locations and geological features

fig:core

32 LBNF reviewed the analysis performed by Arup by enlisting industry leaders as part of a Neutrino
33 Cavity Advisory Board (NCAB). This board reviewed the approach and results of the geotechnical
34 investigation program as well as the preliminary excavation design. Their conclusions indicated
1 that no additional drilling would be required to provide design information for the project and the
2 overall design approach was appropriate. The board provided many recommendations that will
3 advance the design, for example, replacement of wire mesh with fiber-reinforced shotcrete in all
4 excavations, reduction of the distance between caverns, and optimization of the ground support
5 aimed at replacing cable support wherever possible.

6 For further details, see Arup's Geotechnical Interpretive Report [11].

7 citation

8 3.2.3 Geologic Conclusions

9 Recovery of rock cores was performed along with geologic mapping to determine if discontinuities
10 in the rock mass exist that could cause difficulties in the excavation and maintenance of the planned
11 caverns. In general, the proposed locations of the excavations appear to be free of problematic
12 structures. This information, along with measurement of in situ stresses, has allowed numerical
13 modeling of the stresses associated with the anticipated excavations. A sample of some of the
14 initial modeling is provided in Figure 3.4.




Figure 3.4: Contour of stress safety factor indicating influences between caverns

fig:cont

¹⁵ References

- ¹⁶ [1] LBNF/DUNE, “LBNF/DUNE Conceptual Design Report (CDR),” tech. rep., 2015. DUNE
¹⁷ Doc 180-183.
- ¹ [2] Particle Physics Project Prioritization Panel, “Building for Discovery; Strategic Plan for U.S.
² Particle Physics in the Global Context,” 2014. http://science.energy.gov/~/media/hep/hepap/pdf/May%202014/FINAL_P5_Report_Interactive_060214.pdf.
- ⁴ [3] CERN Council, “The European Strategy for Particle Physics, Update 2013,” 2013. <http://council.web.cern.ch/council/en/EuropeanStrategy/ESParticlePhysics.html>.
- ⁶ [4] LBNF/DUNE, “LBNF/DUNE Science Requirements,” tech. rep., 2015. DUNE Doc 112.
- ⁷ [5] Arup, “LBNF FSCF 100% Preliminary Design Report ,” tech. rep., 2015. DUNE Doc 136.
- ⁸ [6] LBNF/DUNE, “Design Report: The LBNF and DUNE Projects,” tech. rep., 2015. DUNE
⁹ Doc ???
- ¹⁰ [7] D. Collaboration, “DUNE/LBNF CDR Volume 2: The Physics Program for DUNE at LBNF,”
¹¹ tech. rep., 2015. DUNE Doc 181.
- ¹² [8] L. Project, “Design Report: The Long-Baseline Neutrino Facility for DUNE,” tech. rep., 2015.
¹³ DUNE Doc ???
- ¹⁴ [9] D. Collaboration, “DUNE/LBNF CDR Volume 4: The DUNE Detectors at LBNF,” tech.
¹⁵ rep., 2015. DUNE Doc 183.
- ¹⁶ [10] LBNF, “LBNF Draft Comprehensive Logistics Report,” tech. rep., 2015. DUNE Doc 423.