


¹
²The Long-Baseline Neutrino Facility (LBNF)
Far Site Facilities

³Preliminary Design Report



⁵

October 5, 2015

Contents

1	Contents	i
3	List of Figures	iii
4	List of Tables	iv
5	1 Introduction	1
6	1.1 The Long-Baseline Neutrino Facility for DUNE	1
7	1.2 Introduction to the Far Site Conventional Facilities	3
8	1.3 Structure of this Report	4
9	2 Project Management	5
10	2.1 Project Structure and Responsibilities	5
11	2.2 SDSTA and SURF	6
12	2.3 CERN	8
13	2.4 Coordination within LBNF	8
14	2.5 LBNF/DUNE Advisory and Coordinating Structures	9
15	2.5.1 International Advisory Council (IAC)	9
16	2.5.2 Resources Review Boards (RRB)	11
17	2.5.3 Fermilab, the Host Laboratory	12
18	2.5.4 DUNE Collaboration	13
19	2.5.5 Long-Baseline Neutrino Committee (LBNC)	13
20	2.5.6 Experiment-Facility Interface Group (EFIG)	13
21	3 Existing Site Conditions	15
22	3.1 Existing Site Conditions Evaluation	15
23	3.2 Evaluation of Geology and Existing Excavations	18
24	3.2.1 Geologic Setting	19
25	3.2.2 Rock Mass Characteristics: LBNF	19
26	3.2.3 Geologic Conclusions	21
27	4 Surface Facility	22
28	4.1 Existing Surface Facility	22
29	4.2 Surface Buildings	22
30	4.2.1 Ross Dry	23
31	4.2.2 Ross Headframe and Hoist Buildings	26
32	4.2.3 Ross Crusher Building	26

1	4.3 New Surface Infrastructure	29
2	5 Underground Excavation	30
3	5.1 LBNF Cavities	30
4	5.1.1 Detector Cavities	30
5	5.1.2 Structure and Cranes	32
6	5.2 LBNF Central Utility Cavern	33
7	5.3 Access/Egress Drifts	33
8	5.4 Excavation Sequencing	33
9	5.5 Interfaces between DUNE, Cryogenics and Excavation	34
10	6 Underground Infrastructure	35
11	6.1 Fire/Life Safety Systems	36
12	6.2 Shafts and Hoists	37
13	6.2.1 Ross Shaft	37
14	6.2.2 Yates Shaft	39
15	6.3 Ventilation	39
16	6.4 Electrical	41
17	6.4.1 Normal Power	41
18	6.4.2 Standby and Emergency Power	41
19	6.4.3 Fire Alarm and Detection	42
20	6.4.4 Lighting	42
21	6.4.5 Grounding	42
22	6.5 Plumbing	43
23	6.5.1 Industrial Water	43
24	6.5.2 Potable Water	43
25	6.5.3 Chilled Water	43
26	6.5.4 Fire Suppression	44
27	6.5.5 Drainage	44
28	6.5.6 Sanitary Drainage	44
29	6.5.7 Nitrogen and Argon Gas Piping	44
30	6.6 Cyberinfrastructure	44
31	6.7 Waste Rock Handling	46
32	References	47

List of Figures

2	1.1	Underground cavern layout	2
3	1.2	Far Site: Main components at the 4850 level	3
4	2.1	LBNF Work Breakdown Structure (WBS) to level 3	6
5	2.2	LBNF organization	7
6	2.3	Joint LBNF/DUNE management structure	10
7	3.1	Regional context showing the city of Lead, South Dakota	16
8	3.2	SURF Complex shown in the context of the city of Lead, South Dakota	17
9	3.3	LBNF core locations and geological features	20
10	3.4	Contour of stress safety factor	21
11	4.1	Architectural site plan	23
12	4.2	Ross Complex architectural site plan	24
13	4.3	Architectural layout of LBNF Cryogenics Compressor Building	25
14	4.4	Photo of Ross Dry exterior	26
15	4.5	Location of new Command and Control Center, main floor	27
16	4.6	Location of new Command and Control Center, basement	28
17	5.1	Spaces required for LBNF at 4850L	31
18	5.2	Dimensions of the main LBNF cavern excavations	32
19	6.1	Ross Shaft, typical shaft set	38
20	6.2	Existing Yates Shaft layout	40
21	6.3	Fiber distribution system for LBNF	45
22	6.4	Waste rock handling system route	46

23

1 List of Tables

2	6.1 Environmental design criteria (Arup)	40
---	----------------------------------------------------	----

3

1 Todo list

2 now part of LBNF/beamline, right?	2
3 from CDR vol 3 ch 2	5
4 from CDR vol 1 4.2	6
5 new reference; is it available?	8
6 from CDR vol 1 sec 4.4	9
7 I don't find this; probably described in cryo annex	22
8 Need orig; too fuzzy	26
9 Josh says: Need to determine whether this terminology is acceptable from Pepin	46

¹⁰ Chapter 1

¹ Introduction

² 1.1 The Long-Baseline Neutrino Facility for DUNE

³ The global neutrino physics community is developing a multi-decade physics program to measure
⁴ unknown parameters of the Standard Model of particle physics and search for new phenomena.
⁵ The program will be carried out as an international, leading-edge, dual-site experiment for neutrino
⁶ science and proton decay studies, which is known as the *Deep Underground Neutrino Experiment*
⁷ (*DUNE*). The detectors for this experiment will be designed, built, commissioned and operated
⁸ by the international DUNE Collaboration. The facility required to support this experiment, the
⁹ *Long-Baseline Neutrino Facility* (*LBNF*), is hosted by the Fermi National Accelerator Laboratory
¹⁰ (Fermilab) and its design and construction is organized as a DOE/Fermilab project incorporating
¹¹ international partners.

¹² Together LBNF and DUNE will comprise the world's highest-intensity neutrino beam at Fermilab,
¹³ in Batavia, IL, a high-precision near detector on the Fermilab site, a massive liquid argon time-
¹⁴ projection chamber (LArTPC) far detector installed deep underground at the Sanford Underground
¹⁵ Research Facility (SURF), 1,300 km away in Lead, SD, and all of the conventional and technical
¹⁶ facilities necessary to support the beamline and detector systems.

¹⁷ The strategy for executing the experimental program was presented in the LBNF/DUNE Con-
¹⁸ ceptual Design Report (CDR)^{cd-1r-cdr}[1]. The program has been developed to meet the requirements set
¹⁹ out in the P5 report^{p5-report-044}[2] and takes into account the recommendations of the European Strategy
²⁰ for Particle Physics[3]. It adopts a model in which U.S. and international funding agencies share
²¹ costs on the DUNE detectors, and CERN and other participants provide in-kind contributions to
²² the supporting infrastructure of LBNF. LBNF and DUNE will be tightly coordinated as DUNE
²³ collaborators design the detectors and infrastructure that will carry out the scientific program.

²⁴ The scope of LBNF is

- ²⁵ • an intense neutrino beam aimed at the far site

- 26 • a beamline measurement system at the near site

1 now part of LBNF/beamline, right?

- 2 • conventional facilities at both the near and far sites
3 • cryogenics infrastructure to support the DUNE detector at the far site

4 The DUNE detectors include

- 5 • a high-performance neutrino detector located a few hundred meters downstream of the neu-
6 trino source
7 • a massive liquid argon time-projection chamber (LArTPC) neutrino detector located deep
8 underground at the far site

9 The scope of LBNF at SURF includes both conventional facilities (CF) and cryogenics infras-
10 tructure to support the DUNE far detector. The requirements on LBNF derive from DUNE
11 Collaboration science requirements[4], which drive the space and functions necessary to construct
12 and operate the far detector. Environment, Safety and Health (ES&H) and facility operations
13 requirements also provide input to the design. The DUNE far detector is designed as a set of four
14 10-kt fiducial mass modules. The caverns and the services to the caverns will be as similar to one
15 another as possible to enable efficiency in design and construction as well as operation. Figure 1.1
16 shows the layout of the underground caverns that will house the detector modules, with a separate
17 cavern to house utilities and cryogenics systems.




Figure 1.1: Underground cavern layout (SRK, Courtesy SURF)

18 1.2 Introduction to the Far Site Conventional Facilities

1 This PDR presents the scope and necessary steps required to develop the LBNF Far Site Conven-
2 tional Facilities (FSCF) at SURF. The key element of the FSCF is the underground space required
3 to install and support the operations of the multi-module DUNE far detector. An overview of the
4 4850L at SURF where the underground facilities will be developed is shown in Figure 1.2. fig:fs-main-components

Figure 1.2: Far Site: Main components at the 4850 level (underground)

5 While the SURF site already meets many requirements from the geological, scientific and engi-
6 neering standpoint, significant work is required to provide adequate space and the infrastructure
7 support needed for the experiment’s installation and operation. The present and future state of the
8 site, evaluation and assessments of the facilities and the associated provisioning of infrastructure
9 such as power, water, plumbing, ventilation, etc., are described in this report. Also described are
10 the safety measures and planned steps to develop the surface and underground structures.

11 The scope of the FSCF includes design and construction for facilities on the surface and un-
12 derground at SURF. The underground conventional facilities include new excavated spaces at
13 the 4850L for the detector, utility spaces for experimental equipment, utility spaces for facility
14 equipment, drifts for access, as well as construction-required spaces. Underground infrastructure
15 provided by FSCF for the experiment includes power to experimental equipment, cooling systems
16 and cyberinfrastructure. Underground infrastructure necessary for the facility includes domestic
17 (potable) water, industrial water for process and fire suppression, fire detection and alarm, normal
18 and standby power systems, a sump pump drainage system for native and leak water around the
19 detector, water drainage to the facility-wide pump discharge system, and cyberinfrastructure for
20 communications and security. In addition to providing new spaces and infrastructure underground,
21 FSCF enlarges and provides infrastructure in some existing spaces for use, such as the access drifts
22 from the Ross Shaft to the new caverns. New piping is provided in the shaft for cryogens (gas
23 argon transfer line and nitrogen compressor suction and discharge lines) and water as well as power
24 conduits and cyberinfrastructure.

25 As it exists today, SURF has many surface buildings and utilities, some of which will be utilized for
26 LBNF. The scope of the above ground FSCF includes only that work necessary for LBNF, and not
27 for the general rehabilitation of buildings on the site, which remains the responsibility of SURF.
28 Electrical substations and distribution will be upgraded to increase power and provide standby
29 capability for life safety. Additional surface scope includes remodeling of an existing building for
30 both office space and to house an experiment/facility control room, and a new building to support
31 cryogen transfer from the surface to the underground near the existing Ross Shaft. To reduce risk
32 of failure of essential but aging support equipment during the construction and installation period,
33 several SURF infrastructure-reliability activities are included as early activities in LBNF. These
34 include completion of the Ross Shaft rehabilitation, rebuilding of hoist motors, and replacement
35 of the Oro Hondo fan; if not addressed, failure of any of this aging infrastructure could limit or
36 stop access to the underground.

37 This PDR is supported by a Design Report from the independent engineering firm, ARUParup:fscf100pdr.

³⁸ 1.3 Structure of this Report

- ¹ The scope of this Preliminary Design Report (PDR) is limited to the LBNF Far Site Conventional
² Facilities (FSCF); the cryogenics infrastructure is not included.
- ³ 1. This chapter provides a short introduction to LBNF, DUNE and the FSCF.
- ⁴ 2. Chapter 2 ^{ch:intro-pm} summarizes the management structure for LBNF.
- ⁵ 3. Chapter 3 ^{ch:fscf-site-cond} describes the existing site conditions at SURF.
- ⁶ 4. Chapter 4 ^{ch:fscf-surf-facil} describes the existing and planned surface buildings that will support the DUNE
⁷ far detector, planned for installation at the 4850L of SURF.
- ⁸ 5. Chapter 5 ^{ch:fscf-excav} discusses the planned underground excavation.
- ⁹ 6. Chapter 6 ^{ch:fscf-und-infra} describes the underground infrastructure that will directly interface to the DUNE
¹⁰ far detector modules.

¹¹ Chapter 2

¹ Project Management

intro-pm

² 2.1 Project Structure and Responsibilities

³ The LBNF Project is charged by Fermilab and DOE to design and construct conventional and technical facilities needed to support the DUNE Collaboration. LBNF is organized as a DOE/Fermilab project incorporating in-kind contributions from international partners. At this time, the major international partner is CERN, the European Organization for Nuclear Research. LBNF works closely with DUNE through several coordinating groups to ensure scientific direction and coordination for executing the LBNF Project such that the requirements of the program are met.

⁹ LBNF works closely with SURF management to coordinate design and construction for the far site conventional facilities for the DUNE far detector. CERN is providing cryogenics equipment and engineering as part of the cryogenics infrastructure at SURF. The design and construction of LBNF is supported by other laboratories and consultants/contractors that provide scientific, engineering, and technical expertise. A full description of LBNF Project Management is contained in the LBNF/DUNE Project Management Plan^[?].

¹⁵ LBNF coordinates with DUNE through regular technical team interactions between the two Projects as well as more formally through the Joint Management Team where day-to-day management coordination occurs, and the Experiment-Facility Interface Group, where major issues regarding interfaces and items affecting both Projects are discussed. In addition, the Projects share common Project Office staff and systems, and include a single, integrated project resource-loaded schedule and configuration management system.

²¹ from CDR vol 3 ch 2

²² LBNF consists of two major L2 subprojects, Far Site Facilities and Near Site Facilities, coordinated through a central Project Office located at Fermilab. Each L2 Project consists of two large L3 subprojects corresponding to the conventional and technical facilities, respectively, at each site. ²⁴ The project organizational structure, which includes leadership from major partners, is shown in

²⁶ Figure 2.1.

¹ from CDR vol 1 4.2

² The LBNF Project team consists of members from Fermilab, CERN, South Dakota Science and
³ Technology Authority (SDSTA), and BNL. The team, including members of the Project Office as
⁴ well as the L2 and L3 managers for the individual subprojects, is assembled by the Project Director.
⁵ The Project team is shown to WBS Level 3 in Figure 2.2. Line management for environment, safety
⁶ and health, and quality assurance flows through the Project Director.

⁷ Through their delegated authority and in consultation with major stakeholders, the L2 Project
⁸ Managers determine which of their lower-tier managers will be Control Account Managers (CAMs)
⁹ for the Project WBS. L2 and L3 Project Managers are directly responsible for generating and
¹⁰ maintaining the cost estimate, schedule, and resource requirements for their subprojects and for
¹¹ meeting the goals of their subprojects within the accepted baseline cost and schedule.




Figure 2.1: LBNF Work Breakdown Structure (WBS) to level 3

fig:lbnf

¹² 2.2 SDSTA and SURF

¹³ LBNF plans to construct facilities at SURF to house the DUNE far detector. SURF is owned by
¹⁴ the state of South Dakota and managed by the SDSTA.

¹⁵ Current SURF activities include operations necessary for allowing safe access to the 4850L of the
¹⁶ former mine, which houses the existing and under-development science experiments. The DOE
¹⁷ is presently funding SDSTA ongoing operations through Lawrence Berkeley National Laboratory
¹⁸ (LBNL) and its SURF Operations Office through FY16; this is expected to change to funding
¹⁹ through Fermilab starting in FY17.

²⁰ The LBNF Far Site Facilities Manager is also an employee of SDSTA and is contracted to Fer-




Figure 2.2: LBNF organization

fig:lbnf

21 milab to provide management and coordination of the Far Site Conventional Facilities (CF) and
1 Cryogenics Infrastructure subprojects. LBNF contracts directly with SDSTA for the design of the
2 required CF at SURF; whereas the actual construction of the CF will be directly contracted from
3 Fermilab. Coordination between SDSTA and the LBNF Project is necessary to ensure efficient
4 operations at SURF. This will be facilitated via an agreement between SDSTA and Fermilab

5 new reference; is it available?

6 that defines responsibilities and methods for working jointly on LBNF Project design and con-
7 struction. A separate agreement will be written for LBNF Operations.

8 **2.3 CERN**

9 The European Organization for Nuclear Research (CERN) is expected to significantly contribute
10 to LBNF with technical components, required to support the deployment of the DUNE detectors
11 and of the neutrino beamline.

12 **2.4 Coordination within LBNF**

13 The LBNF Project organization is headed by the LBNF Project Director, who is also the Fermilab
14 Deputy Director for LBNF; this person reports directly to the Fermilab Director.

15 Within Fermilab's organization, two new divisions are being created to execute the Far Site Fa-
16 cilities and Near Site Facilities subprojects. The heads of these divisions will report to the LBNF
17 Project Manager. Any personnel working more than half-time on these subprojects would typi-
18 cally be expected to become a member of one of these divisions, while other contributors will likely
19 be matrixed in part-time roles from other Fermilab Divisions. The heads of the other Fermilab
20 Divisions work with the L1 and L2 project managers to supply the needed resources on an annual
21 basis. The management structure described above is currently being transitioned into and will not
22 be fully in place until the Fall of 2015.

23 The LBNF WBS defines the scope of the work. All changes to the WBS must be approved by
24 the LBNF Project Manager prior to implementation. At the time of CD-1-Refresh, the LBNF
25 WBS is in transition. Both the current (post CD-1-Refresh Review) WBS is shown in Figure 2.1
26 to demonstrate how the scope will map from one WBS to the other. SDSTA assigns engineers
27 and others as required to work on specific tasks required for the LBNF Project at the SURF site.
28 This is listed in the resource-loaded schedule as contracted work from Fermilab for Far Site CF
29 activities. CERN and Fermilab are developing a common cryogenics team to design and produce
30 the Cryogenics Infrastructure subproject deliverables for the far site. CERN provides engineers
31 and other staff as needed to complete their agreed-upon deliverables. LBNF has formed several
32 management groups with responsibilities as described below.

³³ **Project Management Board:** LBNF uses a Project Management Board to provide formal
¹ advice to the Project Director on matters of importance to the LBNF Project as a whole. Such
² matters include (but are not limited to) those that

- ³ • have significant technical, cost, or schedule impact on the Project
- ⁴ • have impacts on more than one L2 subproject
- ⁵ • affect the management systems for the Project
- ⁶ • have impacts on or result from changes to other Projects on which LBNF is dependent
- ⁷ • result from external reviews or reviews called by the Project Director

⁸ The Management Board serves as the

- ⁹ • LBNF Change Control Board, as described in the Configuration Management Plan^[?] CMP-10760
- ¹⁰ • Risk Management Board, as described in the Fermilab Risk Management Procedure for
¹¹ Projects ^{final-risk-mgmt} [?]

¹² **FSCF Neutrino Cavity Advisory Board:** The Far Site CF (FSCF) Project has engaged three
¹³ international experts in hard rock underground construction to advise it periodically through the
¹⁴ design and construction process regarding excavation at SURF. The Board meets at the request of
¹⁵ the FSCF-PM, generally on site to discuss specific technical issues. The Board produces a report
¹⁶ with its findings and conclusions for Project information and action.

¹⁷ 2.5 LBNF/DUNE Advisory and Coordinating Structures

¹⁸ from CDR vol 1 sec 4.4

¹⁹ A set of structures is established to provide coordination among the participating funding agencies,
²⁰ oversight of the LBNF and DUNE projects, and coordination and communication between the two
²¹ projects. These structures and the relationships among them are shown in Figure 2.3 and are
²² described in this section. fig:lbndune-org

²³ 2.5.1 International Advisory Council (IAC)

²⁴ The International Advisory Council (IAC) is composed of regional representatives, such as CERN,
²⁵ and representatives of funding agencies that make major contributions to LBNF infrastructure or
²⁶ to DUNE. The IAC acts as the highest-level international advisory body to the U.S. DOE and
²⁷ the FNAL Directorate and facilitates high-level global coordination across the entire enterprise




Figure 2.3: Joint LBNF/DUNE management structure

fig:lbnf

28 (LBNF and DUNE). The IAC is chaired by the DOE Office of Science Associate Director for High
1 Energy Physics and includes the FNAL Director in its membership. The council meets as needed
2 and provides pertinent advice to LBNF and DUNE through the Fermilab Director.

3 Specific responsibilities of the IAC include, but are not limited to, the following:

- 4 • During the formative stages of LBNF and DUNE the IAC helps to coordinate the sharing
5 of responsibilities among the agencies for the construction of LBNF and DUNE. Individual
6 agency responsibilities for LBNF will be established in bilateral international agreements with
7 the DOE. Agency contributions to DUNE will be formalized through separate agreements.
- 8 • The IAC assists in resolving issues, especially those that cannot be resolved at the Resources
9 Review Boards (RRB) level, e.g., issues that require substantial redistributions of responsi-
10 bilities among the funding agencies.
- 11 • The IAC assists as needed in the coordination, synthesis and evaluation of input from Project
12 reports charged by individual funding agencies, LBNF and DUNE Project management,
13 and/or the IAC itself, leading to recommendations for action by the managing bodies.

14 The DUNE Co-Spokespersons and/or other participants within the Fermilab neutrino program
15 will be invited to sessions of the IAC as needed. Council membership may increase as additional
16 funding agencies from certain geographic regions make major contributions to LBNF and DUNE.

17 **2.5.2 Resources Review Boards (RRB)**

18 The Resources Review Boards (RRB) are composed of representatives of all funding agencies
19 that sponsor LBNF and DUNE, and of the Fermilab management. The RRB provides focused
20 monitoring and detailed oversight of each of the Projects. The Fermilab Director in coordination
21 with the DUNE RC defines its membership. A representative from the Fermilab Directorate chairs
22 the boards and organize regular meetings to ensure the flow of resources needed for the smooth
23 progress of the enterprise and for its successful completion. The managements of the DUNE
24 Collaboration and the LBNF Project participates in the RRB meetings and make regular reports
25 to the RRB on technical, managerial, financial and administrative matters, as well as status and
26 progress of the DUNE Collaboration.

27 There are two groups within the RRB: RRB-LBNF and RRB-DUNE. Each of these groups monitors
28 progress and addresses the issues specific to its area while the whole RRB deals with matters that
29 concern the entire enterprise. The RRB will meet biannually; these meetings will start with a
30 plenary opening session and be followed by RRB-LBNF and RRB-DUNE sessions. As DUNE
31 progresses toward experimental operations, RRB-Computing sessions will convene.

32 DUNE Finance Board members who serve as National Contacts from the sponsoring funding
33 agencies will be invited to RRB sessions.

34 The RRB employs standing DUNE and LBNF *Scrutiny Groups* as needed to assist in its responsi-

35 bilities. The scrutiny groups operate under the RRB, and provide detailed information on financial
1 and personnel resources, costing, and other elements under the purview of the RRB.

2 Roles of the RRB includes:

- 3 • assisting the DOE and the FNAL Directorate, with coordinating and developing any required
4 international agreements between partners
- 5 • monitoring and overseeing the Common Projects and the use of the Common Funds
- 6 • monitoring and overseeing general financial and personnel support
- 7 • assisting the DOE and the FNAL Directorate with resolving issues that may require reallo-
8 cation of responsibilities among the Project's funding agencies
- 9 • reaching consensus on a maintenance and operation procedure, and monitoring its function
- 10 • approving the annual construction, and maintenance and operation common fund budget of
11 DUNE

12 **2.5.3 Fermilab, the Host Laboratory**

13 As the host laboratory, Fermilab has a direct responsibility for the design, construction, commis-
14 sioning and operation of the facilities and infrastructure (LBNF) that support the science program.
15 In this capacity, Fermilab reports directly to the DOE through the Fermilab Site Office (FSO).
16 Fermilab also has an important oversight role for the DUNE Project itself as well as an impor-
17 tant coordination role in ensuring that interface issues between the two Projects are completely
18 understood.

19 Fermilab's oversight of the DUNE Collaboration and detector construction project is carried out
20 through

- 21 • regular meetings with the Collaboration leadership
- 22 • approving the selection of Collaboration spokespersons
- 23 • providing the Technical and Resource Coordinators
- 24 • convening and chairing the Resources Review Boards
- 25 • regular scientific reviews by the PAC and LBNC
- 26 • Director's Reviews of specific management, technical, cost and schedule aspects of the de-
27 tector construction project

- 28 • other reviews as needed

1 **2.5.4 DUNE Collaboration**

2 The Collaboration, in consultation with the Fermilab Director, is responsible for forming the
3 international DUNE Project team responsible for designing and constructing the detectors. The
4 Technical Coordinator (TC) and Resource Coordinator (RC) serve as the lead managers of this
5 international project team and are selected jointly by the spokespersons and the Fermilab Director.
6 Because the international DUNE Project incorporates contributions from a number of different
7 funding agencies, it is responsible for satisfying individual tracking and reporting requirements
8 associated with the different contributions.

9 **2.5.5 Long-Baseline Neutrino Committee (LBNC)**

10 The Long-Baseline Neutrino Committee (LBNC), composed of internationally prominent scientists
11 with relevant expertise, provides external scientific peer review for LBNF and DUNE regularly.
12 The LBNC reviews the scientific, technical and managerial decisions and preparations for the
13 neutrino program. It acts in effect as an adjunct to the Fermilab Physics Advisory Committee
14 (PAC), meeting on a more frequent basis than the PAC. The LBNC may employ DUNE and LBNF
15 Scrutiny Groups for more detailed reports and evaluations. The LBNC members are appointed by
16 the Fermilab Director.

17 **2.5.6 Experiment-Facility Interface Group (EFIG)**

18 Close and continuous coordination between DUNE and LBNF is required to ensure the success
19 of the combined enterprise. An Experiment-Facility Interface Group (EFIG) was established in
20 January 2015 to oversee and ensure the required coordination both during the design/construction
21 and operational phases of the program. This group covers areas including:

- 22 • interface between the near and far detectors and the corresponding conventional facilities
23 • interface between the detector systems provided by DUNE and the technical infrastructure
24 provided by LBNF
25 • design and operation of the LBNF neutrino beamline

26 The EFIG is chaired by two deputy directors of Fermilab. Its membership includes the LBNF
27 Project Director, Project Manager and Project Scientist, and the DUNE Co-Spokespersons, Tech-
28 nical Coordinator, Resource Coordinator and the CERN-LBNF Project Manager. In consultation
29 with the DUNE and LBNF management, the EFIG Chairs will extend the membership as needed
30 to carry out the coordination function. In addition, the DOE Federal Project Director for LBNF,

31 the Fermilab Chief Project Officer, and a designated representative of the South Dakota Science
1 and Technology Authority (SDSTA) will serve ex officio. The EFIG Chairs designate a Secretary
2 of the EFIG, who keeps minutes of the meetings and performs other tasks as requested by the
3 Chair.

4 It is the responsibility of the EFIG Chairs to report EFIG proceedings to the Fermilab Director and
5 other stakeholders. It is the responsibility of the DUNE spokespersons to report EFIG proceedings
6 to the rest of the Collaboration. The EFIG meets weekly or as needed.

7 Chapter 3

1 Existing Site Conditions

ite-cond
2 The SDSTA currently operates and maintains the Sanford Underground Research Facility (SURF)
3 at the former Homestake mine in Lead, South Dakota. The SURF property comprises 186 acres
4 on the surface and 7,700 acres underground. The SURF Surface Campus includes approximately
5 253,000 gross square feet (gsf) of existing structures. Using a combination of private funds through
6 T. Denny Sanford, South Dakota Legislature-appropriated funding, and a federal Department
7 of Housing and Urban Development (HUD) Grant, the SDSTA has made significant progress
8 in stabilizing and rehabilitating the SURF facility to provide for safe access and prepare the
9 site for new laboratory construction. These efforts have included dewatering of the underground
10 facility and mitigating and reducing risks independent of the former Deep Underground Science
11 and Engineering Laboratory (DUSEL) efforts and funding.

12  Figure 3.1 shows SURF's location within the region as a part of the northern Black Hills of South
13  Dakota. Figure 3.2 outlines the SURF site in relationship to the city of Lead, South Dakota, and
14 points out various significant features of Lead including the surrounding property that still remains
15 under the ownership of Barrick Gold Corporation.

16 3.1 Existing Site Conditions Evaluation

ond-eval
17 The existing facility conditions were assessed as part of the DUSEL Preliminary Design and docu-
18 mented in the DUSEL PDR, Section 5.2.4, [10] which is excerpted below. The portions of DUSEL's
19 assessment included here have been edited to reflect current activities and to reference only that
20 portion of the assessment that are pertinent to the LBNF Project. References to the DUSEL
21 Project are from that time, and are now considered historic.

22 Site and facility assessments were performed during DUSEL's Preliminary Design phase by HDR
23 to evaluate the condition of existing facilities and structures on the Yates, and Ross Campuses.
24 The assessments reviewed the condition of buildings proposed for continuing present use, new
25 use, or potential demolition. Building assessments were performed in the categories of architec-




Figure 3.1: Regional context showing the city of Lead, South Dakota. (Dangermond Keane Architecture, Courtesy SURF)

fig:regi




Figure 3.2: SURF Complex shown in the context of the city of Lead, South Dakota, and the property remaining under ownership of Barrick. Area shown in yellow is a potential future expansion of the SDSTA property. [Dangermond Keane Architecture, Courtesy of SURF]

fig:surf

tural, structural, mechanical/electrical/plumbing (MEP), civil, environmental, and historic. Site assessments looked at the categories that included civil, landscape, environmental, and historic. Facility-wide utilities such as electrical, steam distribution lines, water, and sewer systems were also assessed. The assessment evaluation was completed in three phases. The detailed reports are included in the appendices of the DUSEL PDR as noted and are titled:

- Phase I Report, Site Assessment for Surface Facilities and Campus Infrastructure to Support Laboratory Construction and Operations (DUSEL PDR Appendix 5.E)
- Phase II Site and Surface Facility Assessment Project Report (DUSEL PDR Appendix 5.F)
- Phase II Roof Framing Assessment (DUSEL PDR Appendix 5.G)

The site and facility assessments outlined above were performed during DUSEL's Preliminary Design as listed above and includes a review of the following:

- Buildings proposed for reuse were evaluated for preliminary architectural and full structural, environmental, and historic assessments
- Buildings proposed for demolition were evaluated for preliminary historic assessments
- Preliminary MEP assessments were performed on the Ross Substation, #5 Shaft fan, Oro Hondo fan, Oro Hondo substation, and general site utilities for the Ross, Yates, and Ellison Campuses
- The waste water treatment plant (WWTP) received preliminary architectural and structural assessments and a full MEP assessment
- Preliminary civil assessments of the Kirk Portal site and Kirk to Ross access road were also completed.

3.2 Evaluation of Geology and Existing Excavations

LBNF Far Site facilities are planned to be constructed at SURF which is being developed within the footprint of the former Homestake Gold Mine, located in Lead, South Dakota. The accessible underground mine workings are extensive. Over the life of the former gold mine over 360 miles of drifts (tunnels) were mined and shafts and winzes sunk to gain access to depths in excess of 8,000 feet. A number of underground workings are being refurbished by SURF and new experiments are being developed at the 4850L, the same level as proposed for LBNF facilities. Geotechnical investigations and initial geotechnical analyses were completed for the DUSEL Preliminary Design [10] and are described in detail in the DUSEL PDR. Additional geotechnical investigation and analysis was performed in 2014 specific to the LBNF project. Below are summaries these two effort, including work completed for DUSEL that is applicable to LBNF as excerpted from the DUSEL Preliminary Design Report, Chapter 5.3. Much of the work completed for the alternative

33 detector technology considered during DUSEL [water Cherenkov detector (WCD)] is also applicable
1 to the current design at the 4850L.

2 3.2.1 Geologic Setting

3 SURF is sited within a metamorphic complex containing the Poorman, Homestake, Ellison and
4 Northwestern Formations (oldest to youngest), which are sedimentary and volcanic in origin. An
5 amphibolite unit (Yates Member) is present within the lower known portions of the Poorman
6 Formation. While the Yates Member is the preferred host rock for the LBNF excavations at 4850L,
7 the LBNF cavity has been located in the Poorman formation to isolate it from the remainder of the
8 level. The layout adopted on the 4850L attempts to optimize the needs for ventilation isolation,
9 access control, and orientation relative to the beam line.

10 3.2.2 Rock Mass Characteristics: LBNF

11 Following a similar strategy as DUSEL, the LBNF project initiated a second geotechnical program
12 in 2013 to evaluate the specific location under consideration and evaluate its appropriateness for
13 the proposed design. This was undertaken in two phases. The first phase was a mapping of the
14 existing spaces surrounding the proposed rock mass using both visual techniques and laser scanning
15 to understand the rock mass and inform the scope of the second phase. The second phase included
16 drilling of four HQ (2.5-in diameter) core holes ranging in length from 477 to 801 feet as well as
17 two 6-in diameter core holes ~30 ft each. The smaller diameter cores were then evaluated for the
18 following characteristics:

- 19 • core recovery percent
- 20 • rock quality designation (RQD) percent
- 21 • rock type, including color, texture, degree of weathering, and strength
- 22 • mineralogy and presence of magnetic sulfides
- 23 • character of discontinuities, joint spacing, orientation, aperture
- 24 • roughness, alteration, and infill (if applicable)

25 Representative samples were selected from the overall core to test material strength and chemical
26 characteristics. The [fig:core-loc](#) geotechnical site investigations area on the 4850L, showing boreholes is
27 presented in Figure 3.3.

28 The holes from which the smaller diameter core was removed were studied in several ways. An
29 absolute survey was conducted to allow the core holes to be plotted relative to cavern designs. An
30 optical televiewer was passed through each small hole to visualize the rock mass. This technique

allows visualization of foliation, joint openings, healed joints, and geological contact between rock types. An acoustical imaging device was also used in one hole to complement the optical information. The permeability of the rock was tested by pressurizing the small holes at various intervals to determine if joints allowed for the flow of water outside of the holes (hydraulic conductivity). In all cases, the hydraulic conductivity was well below what can be accomplished using manmade techniques such as grouting. Two of the small holes were plugged and instrumented to determine if water would flow into the holes over time. This test found very low flow rates (.0013 – .0087 gpm). Ongoing evaluation of pressure build in these holes was inconclusive, as blast induce fracturing near the existing drifts allow the holes to depressurize outside of the test instruments.




Figure 3.3: LBNF core locations and geological features

fig:core

The larger (6-in) diameter cores and holes were used for strength and stress testing. In-situ stress was tested by drilling a smaller diameter hole first, then gluing a strain gage at 30 – 36 feet within the depth. As the larger diameter core was removed, this strain gage recorded the relaxation of the rock. The removed core was re-drilled to provide smaller diameter samples at specific orientations for strength testing, as the strength of the material varies based on applied force direction relative to the foliation of the rock. These samples were also tested for time dependent movement.

LBNF followed a review approach for the analysis performed by Arup by enlisting industry leaders as part of a Neutrino Cavity Advisory Board (NCAB). This board reviewed the philosophy and results of the geotechnical investigation program as well as the preliminary excavation design. Their conclusions indicated that no additional drilling would be required to provide design information for the project and the overall design approach was appropriate. They provided many recommendations that will benefit the advancement of design.

For further details, see Arup's Geotechnical Interpretive Report [11].

22 3.2.3 Geologic Conclusions

eo-concl
1 The recovery of rock cores, plus geologic mapping, was performed to determine if discontinuities in
2 the rock mass exist that would cause difficulties in the construction and maintenance of planned
3 excavations. In general, the proposed locations of the excavations do not appear to be complicated
4 by geologic structures that cause undue difficulties for construction. This information, along with
5 measurement of in situ stresses, allowed initial numerical modeling of the stresses associated with
6 the anticipated excavations. A sample of some of the modelling done is provided in Figure 3.4.

Fig:Contour-stres




Figure 3.4: Contour of stress safety factor indicating influences between caverns

fig:cont

7 Chapter 4

1 Surface Facility

2 4.1 Existing Surface Facility

3 The SURF property of 186 acres consists of steep terrain and man-made cuts dating from its mining
4 history. There are approximately 50 buildings and associated site infrastructure in various states
5 of repair. A select few of these buildings at the Ross Complex and the main utilities are needed by
6 the LBNF experiment and will be upgraded and rehabilitated as necessary. A layout of the overall
7 SURF architectural site plan for the LBNF Project is found in Figure 4.1. The Ross Complex will
8 house the facility construction operations, command and control center for the experiment and
9 facility, new cryogenics compressor building, as well as continue to house the SURF maintenance
10 and operations functions. Layout of surface facilities in the vicinity of the Ross Shaft is shown in
11 Figure 4.2.

12 4.2 Surface Buildings

13 Surface facilities utilized for the LBNF include those necessary for safe access and egress to the
14 underground through the Ross Shaft, as well as spaces for offices. Existing buildings necessary for
15 LBNF will be rehabilitated to code-compliance and to provide for the needs of the experiment.
16 The only new building will be to provide space for compressors used to transfer cryogens from
17 new receiving tanks on surface to the detectors underground. The existing Ross Dry building will
18 be modified to provide space for a surface control room and offices. Much of the text below is
19 excerpted from the 100% Preliminary Design Report [12] provided by Arup, USA.

20 A new building and surrounding concrete slabs are planned to provide space for equipment to allow
21 conversion of liquid argon and liquid nitrogen to gaseous form and compression of the nitrogen for
22 delivery through the shaft to the underground where they are returned to liquid form as described
23 later in this PDR in Chapter 4.




Figure 4.1: Architectural site plan (HDR)

fig:arch

²⁴ I don't find this; probably described in cryo annex

- 1 The location of this building was selected based on proximity to the shaft and truck accessibility,
- 2 as thousands of truckloads of argon are required to fill the detectors underground.

- 3 In addition to housing nitrogen compressors inside the building, concrete slabs are provided around
- 4 the building to allow for installation of argon and nitrogen receiving dewars for truck unloading,
- 5 vaporizers to boil the liquids into gas, and electrical transformer to supply power to the (4) 1,500
- 6 Hp compressors, a standby generator, and cooling towers to reject heat generated through com-
- 7 pression. All equipment except the cooling towers and associated circulation pumps is provided by
- 8 the Cryogenics Infrastructure Project. The architectural layout of this building and surrounding
- 9 equipment is provided in Figure 4.3.

¹⁰ 4.2.1 Ross Dry

- 11 The Ross Dry building is in use by SURF to provide office and meeting space in addition to men's
- 12 and women's dry facilities and emergency response capabilities. As a scope option, the design
- 13 has included a complete renovation of this building to upgrade those existing capabilities and add
- 14 space for an above-ground control room. This design includes flexible space that can be tailored
- 15 to individual user's needs as the project transitions from construction through operations.




Figure 4.2: Ross Complex architectural site plan (Arup)

fig:ross




Figure 4.3: Architectural layout of LBNF Cryogenics Compressor Building

fig:comp

- 16 The exterior of the Ross Dry is shown in Figure 4.4. The renovations of this building are shown
1 in Figures 4.5 and 4.6.



Figure 4.4: Photo of Ross Dry exterior (HDR)

Need orig; too fuzzy

fig:ross

4.2.2 Ross Headframe and Hoist Buildings

- 3 The headframe and hoist buildings at the Ross Campus provide services for LBNF use. The Ross
4 Headframe Building will be the main entry point for construction activities as well as the ongoing
5 operations and maintenance functions. Gas pipe from the LBNF Cryogenics Compressor Building
6 will pass through this building to get to the shaft.

4.2.3 Ross Crusher Building

- 8 The existing Ross Crusher Building is a high bay space that contains rock crushing equipment that
9 will be used for construction operations. The exterior of the building will be repaired to create
10 a warm, usable shell. The upgrade of the existing ^{sec:rsct-and-waste-rock} crusher equipment is part of the waste rock
11 handling work scope (see Section 6.7) and not part of the building rehabilitation.




Figure 4.5: Location of new Command and Control Center (SURF), main floor.

fig:cmd-




Figure 4.6: Location of new Command and Control Center (SURF), basement.

fig:cmd-

12 4.3 New Surface Infrastructure

face-new

- 1 Surface infrastructure includes surface structures such as retaining walls and parking lots, as well
2 as utilities to service both buildings and underground areas. Existing infrastructure requires both
3 rehabilitation as well as upgrading to meet code requirements and LBNF needs. The experiment
4 needs were documented in the requirements found in LBNF Requirements Document[4] and com-
5 bined with facility needs for the design detailed in the Arup 100% Preliminary Design Report[5].
dune-sci-req
arup:fscf100pd
- 6 No new roads or parking lots are required for LBNF at SURF. The Ross Complex site will require
7 minor demolition of power lines and a fire hydrant that are no longer used to provide adequate
8 accessibility for truck traffic to the new Cryogenics Compressor Building. An existing space will
9 be designated for handicap parking adjacent to the Ross Dry Building. Additional road work is
10 required for truck transportation of waste rock, as described in the waste rock handling section.

¹¹ Chapter 5

¹ Underground Excavation

² The main excavated spaces necessary to support the LBNF experiment are a combination of
³ excavations required for the experiment and those required for constructability. Experimental
⁴ spaces on the 4850L include the detector chambers, drifts for access and utility routing, and the
⁵ Central Utility Cavern. Spaces identified as likely necessary for the excavation subcontractor
⁶ include mucking drifts connected to the Ross Shaft to enable waste rock handling and equipment
⁷ assembly shops to provide space to assemble and maintain excavation equipment underground. In
⁸ addition, a spray chamber is provided for heat rejection from the chilled water system. All spaces
⁹ are identified on the 100% Preliminary Design excavation drawings produced by Arup^[5]. The
¹⁰ spaces are shown below in Figure 5.1.

^{Arup, scf100pdr}

¹¹ 5.1 LBNF Cavities

¹² 5.1.1 Detector Cavities

¹³ The required experimental spaces were defined through interaction with the DUNE design team
¹⁴ and are documented in LBNF Requirements Document [14]. The size and depth of the LBNF
¹⁵ cavities were prescribed to suit the scientific needs of the experiment. The overall main cavern
¹⁶ sizes are shown graphically in Figure 5.2. The DUNE experiment will be housed in four detector
¹⁷ chambers within two main caverns at the 4850L. Siting deep underground is required to shield
¹⁸ from cosmic rays, as detailed in Report on the Depth Requirements for a Massive Detector at
¹⁹ Homestake [15]. The 4850L is deeper than what is absolutely required, but is used because of
²⁰ existing access at this level.

²¹ The limits on size for the detector are determined by rock strength and the limits on the ability
²² to produce large dimension anode and cathode plane arrays. Space occupied by the free-standing
²³ steel structure, vessel insulating liner, and an intentional exclusion zone reduce the fiducial volume
²⁴ of the detector below the volume of the excavation. Current assessment of rock quality indicates
²⁵ that a cavity of this size is reasonable with the rock quality assumed for this formation.




Figure 5.1: Spaces required for LBNF at 4850L (SURF)

fig:spac




Figure 5.2: Dimensions of the main LBNF cavern excavations (final dimensions will be slightly smaller). (SURF)

fig:dim-

26 Preliminary modeling of the proposed excavations included 2D and 3D numerical modeling. The
 1 intact rock strength and joint strength had the greatest impact according to the 2D modeling, and
 2 3D modeling confirmed that the complex geometry is possible.

3 The far detector cavity and drifts will be supported using galvanized rock bolts/cables, wire mesh,
 4 and shotcrete for a life of 30 years. The floor of the cavity has been evaluated and does not
 5 require support. A groundwater drainage system will be placed behind the shotcrete in the arch
 6 and walls of the far detector cavity rock excavation. This drain system will collect groundwater
 7 (native) seepage and eliminate the potential for hydrostatic pressure build-up behind the shotcrete.
 8 Channels will be placed in the concrete invert to drain groundwater to the sump system.

5.1.2 Structure and Cranes

9
 10 The LBNF caverns require monorail cranes to facilitate the construction of the detector compo-
 11 nents. Rock bolts will be coordinated with the excavation contractor to provide anchorage to
 12 support these monorails.

13 5.2 LBNF Central Utility Cavern

1 util-cav
2 LBNF requires spaces for cryogenics equipment outside of the detector caverns. These requirements
3 have been combined with that for the conventional facilities utilities in an independent Central
4 Utility Cavern. This area will house the experiment's cryogen system, electrical equipment to
5 supply power for facility and experiment needs, sump pump access and controls, fire sprinkler room,
6 air handling units (AHUs), chilled water system, and ducting. The centralized location minimizes
7 overall utility distribution costs. Isolating the utilities from the experiment simplifies electrical
8 ground isolation to avoid interference with sensitive detector electronics, and also provides the
9 opportunity to optimize ventilation to control heat emanating from the equipment in the Central
Utility Caverns.

10 5.3 Access/Egress Drifts

1 s-drifts
2 In order to accommodate deliveries, the drift connections from the Ross Shaft to new excavations
3 required for LBNF will be optimized to accommodate the maximum load size possible through the
4 shaft plus the utilities required to service the facility. At the writing of this document, an assumed
5 size of 5m wide by 6m tall is used for all access and egress drifts. All new excavations, or drifts
6 enlarged for LBNF will be provided with a shotcrete wall (rib) and ceiling (back) and a concrete
7 floor (sill).

17 5.4 Excavation Sequencing

1 -exc-seq
2 A key goal of both LBNF and DUNE is to complete construction of one 10 kt detector as soon as
3 possible. To facilitate this, the excavation will be sequenced to allow DUNE to begin installation
4 of a cryostat in the first detector chamber while excavation continues. A temporary wall will be
5 built in the detector installation laydown space between detector chambers to isolate one area
6 from another. This wall must be of sturdy construction to withstand air shock waves associated
7 with drill and blast type construction. Further evaluation of vibration limits and controls must be
8 considered as the design advances to avoid damaging the cryostat during assembly.

9 A key concern with
10 sequencing is the impact of blasting on the cryostat.
11 The cryostat is a large, delicate piece of equipment that must be handled carefully during
12 assembly. Blasting can cause significant vibration and pressure waves that could damage the
13 cryostat. Therefore, it is important to coordinate the sequencing of excavation and blasting to
14 minimize the impact on the cryostat.
15 One way to do this is to爆破点 (blast points) the rock mass around the cryostat before
16 beginning excavation. This allows the rock to settle and stabilize before the cryostat is installed.
17 Another approach is to use smaller, more controlled blasts to avoid causing too much
18 vibration and pressure. This requires careful planning and coordination between the
19 excavation team and the blasting team.
20 Overall, sequencing is a critical part of ensuring the safe and successful construction of the
21 detector. By carefully considering the impact of blasting on the cryostat and coordinating the
22 sequencing of excavation and blasting, the project team can minimize risks and ensure a
23 successful outcome.

24 As mentioned earlier, most excavated material will travel through a mucking ramp starting at the base of each detector

34 pit and ending at the waste dump near the Ross Shaft. This route is completely independent
1 of all other traffic and includes a separate ventilation stream to keep diesel exhaust from other
2 occupied spaces. During times when excavation is establishing the upper sections of the caverns
3 and developing a means of dumping excavated material to this lower elevation, material will need to
4 be transported at the 4850L. To alleviate any potential interferences, the first phase of construction
5 will establish a connection from the 4850L to the mucking ramp, as well as ventilation paths to
6 avoid contaminating the air in spaces that have been turned over for cryostat construction.

7 Delivery of cryostat components to the individual pits can be accomplished in one of two ways. All
8 materials are delivered through the shafts to the 4850L, which is 18m above the base of the pits.
9 During construction of the first cryostat, while excavation continues in the other areas, all materials
10 will be delivered to the detector installation laydown area between the first and second detector
11 chambers and/or to the west end of the first detector chamber. An overhead crane will be used
12 to lower this material into the pits. This crane is required for installation of detector component
13 within the cryostat, so is not additional equipment. All excavation will be completed before any
14 construction is required in the third and fourth detector pits, providing the opportunity to use the
15 excavation mucking ramp for delivery of cryostat components. This ramp has been designed at an
16 8% grade to from the west side to allow for this possibility.

17 **5.5 Interfaces between DUNE, Cryogenics and Excavation**

18 There are several points at which the experiment and the facility interface closely. These are
19 managed through discussions between DUNE design team, the Cryogenics Infrastructure design
20 team, and the Conventional Facilities design team and design consultants.

- 21 • The LBNF cryostat is a freestanding structure requiring infrequent access for inspection
22 around the vessel. Low tolerance control in excavation will impact the cost of providing
23 access to inspect this vessel.
- 24 • The utility spaces to house the cryogen system are directly influenced by the size of the
25 cryogen system equipment.
- 26 • The size and construction sequencing of the detector chambers are critical to the experimental
27 strategy.

²⁸ Chapter 6

¹ Underground Infrastructure

- ² nd-infra
- ² The requirements for underground infrastructure for the LBNF Project will be satisfied by a combination of existing infrastructure, improvements to those systems, and development of new infrastructure to suit specific needs. The Project must consider the other tenants underground at SURF for which infrastructure is required, including both the existing Davis Campus experiments and the Ross Campus Experiments. The Ross campus experiments in particular are in relatively close proximity (~150 m) to LBNF.
 - ⁸ The systems must support the LBNF Conventional Facilities (CF) construction activities, Cryogenics Infrastructure, DUNE experiment installation, and operations of both CF Equipment and the experiment. These three scenarios were analyzed and the most demanding requirements chosen from each situation were used to define the requirements for design.
 - ¹² Some of the SURF infrastructure that requires upgrading for LBNF will be rehabilitated prior to the beginning of LBNF construction funding. This includes Ross Shaft rehabilitation, Yates Shaft focused maintenance and repair, and ground support activities at the 4850L between the Yates and Ross Shafts. Additional discussion of this work is included in section 3.5 .
 - ¹⁶ The conceptual underground infrastructure design for LBNF has been performed by several entities. The primary designer referenced in this document is Arup, USA. Arup's scope includes utility provisions and fire protection- life safety (FLS) strategy, covering infrastructure from the surface through the shafts and drifts, to the cavity excavations for the experiment. Utility infrastructure includes fire/life safety systems, permanent ventilation guidance, HVAC, power, plumbing systems, communications infrastructure, lighting and controls, per the experimental utility requirements provided by DUNE and through coordination with LBNF, SURF and the excavation and surface design teams. The design is described in Arup's LBNF 100% Preliminary Design Report^[5] and in the conceptual design drawings. This chapter summarizes the work done by Arup and utilizes information from that report. Arup:fscf100p
 - ²⁶ Shaft rehabilitation and waste rock handling design were previously provided for the DUSEL PDR. This chapter uses excerpts from the DUSEL Preliminary Design Report, Chapter 5.4 [10].
²⁸ The research supporting this work took place in whole or in part at the Sanford Underground

29 Laboratory at Homestake in Lead, South Dakota. Funding for this work was provided by the
1 National Science Foundation through Cooperative Agreements PHY-0717003 and PHY-0940801.
2 The assistance of the Sanford Underground Laboratory at Homestake and its personnel in providing
3 physical access and general logistical and technical support is acknowledged.

4 **6.1 Fire/Life Safety Systems**

5 Life safety is a significant design criterion for underground facilities, focusing on events that could
6 impact the ability to safely escape, or if escape is not immediately possible, isolate people from
7 events underground. Design for fire events includes both preventing spread of fire and removing
8 smoke and/or cryogenic gasses through the ventilation system. The evaluation and establishment
9 of requirements for cryogenic gas removal is performed by the cryogenics group and provided to
10 CF.

11 Life safety requirements were identified and the design developed by Arup, utilizing applicable
12 codes and standards, including NFPA 520: Standard on Subterranean Spaces, which requires
13 adequate egress in the event of an emergency. Facility fire detection and suppression systems, as
14 well as personnel occupancy requirements are defined in accordance with NFPA 101: Life Safety
15 Code. The design was reviewed by Aon Risk Solutions and the recommendations documented
16 in Fire Protection/Life Safety Assessment for the Conceptual Design of the Far Site of the Long
17 Baseline Neutrino Experiment [16]. Due to the unique nature of the experiment and its location, a
18 number of potential variances will require approval from the authority having jurisdiction (AHJ).
19 Significant examples include use of elevators for egress and use of drifts as air *ducts*. The AHJ for
20 Lead, SD is familiar with the facility and the project, and is expected to provide reasonable and
21 timely feedback for proposed variances.

22 Based on data provided by SURF the maximum occupant load of the 4850L will be controlled
23 144 occupants following completion of the Ross Shaft Rehabilitation. This can support the anticipated
24 42 Underground Operations staff, 50 science staff for LBNF (during installation), and 20
25 science staff associated with the existing experiments. A logistics study^[6] was completed by Arup
26 evaluating the occupancy load during CF construction as well, confirming the adequacy of this
27 number.

28 Compartmentation will be needed for egress routes to separate them from adjacent spaces to
29 limit the horizontal and vertical spread of fire and smoke. Use of compartmentation will help
30 to reduce the likelihood of fire and smoke spreading from the area of fire origin to other areas
31 or compartments. Compartmentation will also help limit the spread of other materials such as
32 cryogenic gases, leaks and spills. This results in design criteria of minimum 4-hour fire separation
33 between the LBNF cavities and adjacent drifts, while all rooms that connect directly to the egress
34 drift at 4850L, as well as the shafts, will have 2-hour minimum fire separation.

35 6.2 Shafts and Hoists

1 The Ross and Yates Shafts provide the only access from the surface to the underground, and are
2 therefore critical to the function of the Facility. Both shafts provide service from the surface to the
3 4850L, though not every intermediate level is serviced from both shafts. The shafts also provide a
4 path for all utilities from the surface to the underground.

5 The Ross and Yates Shafts were both installed in the 1930s and have operated since installation.
6 These shafts, along with their furnishings, hoists, and cages, were well maintained during mining
7 operations, but have experienced some deterioration as described in this section. A complete
8 assessment of the Ross and Yates shafts was conducted for the DUSEL Project, and is documented
9 in the Arup Preliminary Infrastructure Assessment Report (DUSEL PDR Appendix 5.M [10]).

10 6.2.1 Ross Shaft

11 The Ross Shaft will be used for facility construction, including waste rock removal, routine facility
12 maintenance, and egress path for the finished underground campuses. It will also be used for
13 LBNF experiment primary access. Excavation for LBNF cannot begin until the Ross Shaft is
14 rehabilitated by SURF.

15 The Ross Shaft is rectangular in shape — 14 ft 0 in (4.27 m) by 19 ft 3 in (5.87 m), measured to
16 the outside of the set steel. The shaft collar is at elevation 5,354.88 ft (1,632.17 m) and the 5000L
17 is the bottom level at elevation 277.70 ft (84.64 m) above sea level. Service is provided to 29 levels
18 and five skip loading pockets. The shaft is divided into seven compartments: cage, counterweight,
19 north skip, south skip, pipe, utility, and ladder way. See Figure 6.1 below showing shaft layout.

20 The Ross Shaft was in operation until the Homestake Gold Mine closed in 2003. Deterioration
21 through corrosion and wear on the shaft steel, including studdles (vertical steel members placed
22 between steel sets), sets, and bearing beams, prompted a full *strip and re-equip* project being
23 performed by SURF. The Ross Shaft layout will not be significantly modified from the existing
24 configuration. The set spacing is being increased from 6 ft to 18 ft, but the general configuration
25 is remaining the same to allow for emergency egress during rehabilitation. The shaft was installed
26 with limited ground support, electing to utilize lacing to prevent spalled rock from reaching the
27 personnel conveyances. The new design replaces this system with a pattern bolting system to
28 control rock movement. The requirements for this shaft are safety, performance, and code driven
29 and defined by the existing configuration. Shaft rehabilitation through calendar year 2016 has been
30 executed by SURF with non-LBNF Project funds. The rehabilitation is just over 60% complete as
31 of this report and is planned to be completed in 2017. Beginning in January 2017, the funding for
32 the balance of the rehabilitation project will come from the LBNF project. This will also include
33 rehabilitation of the skip loading pocket for waste rock handling, and replacement of skips, cage,
34 and ropes..

35 The production and service hoists at the Ross Shaft are located on the surface in a dedicated
36 hoistroom west of the shaft. The service hoist operates the service cage and the production hoist




Figure 6.1: Ross Shaft, typical shaft set (SRK, Courtesy SURF)

fig:ross

37 operates the production skips. The DUSEL PDR describes the condition assessment of the elec-
1 trical and mechanical hoisting systems which are described in detail in the Arup Preliminary
2 Infrastructure Assessment Report (DUSEL PDR Appendix 5.M [10]). These electrical and me-
3 chanical systems will have standard maintenance performed on them to make them in like new
4 condition, but will not be modified from the existing design. The Ross Headframe steel requires
5 some strengthening and modifications to meet code requirements. All of this work is captured in
6 the LBNF scope.

7 **6.2.2 Yates Shaft**

8 The Yates Shaft is rectangular in shapeâ€”15 ft-0 in (4.572 m) by 27 ft-8 in (8.433 m) measured
9 to the outside of the set timbers. There are two cage compartments and two skip compartments
10 as shown in Figure 6.2.  In addition to the cage and skip compartments, there are two other
11 compartments in which shaft services are located. The shaft collar is at 5,310.00 ft (1,618.49 m)
12 elevation and the 4850L is the bottom level at elevation 376.46 ft (114.75 m) above sea level.
13 Service is provided to 18 levels plus four skip-loading pockets. Sets are made up of various length
14 and size timbers located to maintain compartment spaces. The Yates Shaft is timbered except for a
15 fully concrete-lined portion from the collar to the 300L. Recent repairs include full set replacement
16 from the concrete portion to the 800L and additional set repair below this level where deemed
17 critical.

18 The Yates Service Hoist and Production Hoist are planned to be used as existing, with main-
19 tenance performed to bring them into like new condition. Further details regarding the condition
20 of the Yates Hoists' electrical and mechanical condition can be found in Section 2.2 of the Arup
21 Preliminary Site Assessment Report (DUSEL PDR Appendix 5.M) [10].

22 **6.3 Ventilation**

23 The ventilation system will utilize the existing mine ventilation system for most of the distance
24 to the surface, with modifications made near the LBNF caverns to improve capacity. Fresh air for
25 the LBNF cavities and the utility drifts will be provided by pulling air directly from the existing
26 drifts, which is supplied from the Yates and Ross Shafts. Air will be exhausted from the LBNF
27 cavities and utility drifts through a spray chamber rejecting heat from the LBNF chilled water
28 system into new borehole connecting to the 3500 level of the facility, a short distance from the
29 Oro Hondo shaft, which provide direct connection to the fan at the surface. 230,000 cfm design
30 is required for heat extraction. 27,500 cfm passes through the each main experimental area^{tab:env-design-crit}
31 21,500 through the central utility cavern, with the balance of the air required for heat rejection
32 coming directly from the shafts through connections to existing drifts. The environmental design
33 criteria for LBNF underground spaces are shown in Table 6.1.¹

¹During operations, occupancy of the LBNF cavities is 10. Temperature, humidity and filtration requirements in localized areas of these spaces may differ, dependent on requirements. This will be provided by the experiment installation design team. The internal conditions stated above will be used to inform the design of plant and services for each space




Figure 6.2: Existing Yates Shaft layout (Adapted from SRK, Courtesy SURF)

fig:yate

Table 6.1: Environmental design criteria (Arup)

Room	Internal Temperature	Humidity Range	Min. Vent. Rate/ Fresh Air Changes	Occupancy (during assembly)
LBNF Cavities	40 – 82°F (10 – 28 °C)	15 – 85%	1	20(50)
Access Drifts	Min 50°F (10 °C)	Uncontrolled		Transient space
Utility spaces / Electrical rooms	50 – 95 °F (10 – 35 °C)	Uncontrolled	1	
Storage Rooms	59 – 104 °F (15 – 40 °C)	Uncontrolled	Min 15 cfm/person	Room- dependent

ign-crit

34 Per historical data, outdoor temperatures can drop below -20°F ; therefore, the intake air requires
1 heating to prevent ice build-up in the shafts which could potentially disrupt hoisting operations
2 and damage shaft support members, cables and piping. The existing shaft heaters are expected to
3 be adequate for normal operation, but temporary supplemental heating may be necessary during
4 excavation due to higher demands. A study will be performed during final design to determine if
5 waste heat from the cryogenic systems surface compressors can be used for energy savings to heat
6 the intake air.

7 **6.4 Electrical**

8 The underground facilities at the 4850L will have electrical power for normal operations as well as
9 standby power for emergency occupant evacuation. LAr experiment power requires standby power
10 for circulation of cryogens to avoid rapid boil-off and loss of argon.

11 **6.4.1 Normal Power**

12 The estimated electrical loads for both the far detector experiment and the underground infras-
13 tructure serving the experimental spaces are included in the facility load determination and design.

14 Power to serve the far detector experiment will originate from the Ross substation and be routed
15 down the Ross Shaft to the 4850L. One set of 15-kV mining cables shall be installed down the
16 Ross Shaft to the 4850L and shall be cable rated for mine use, highly flame retardant, low smoke
17 toxicity with high tensile strength and self-supporting. At the 4850L, the 15-kV mining cables
18 will terminate in 15-kV switchgear located in a new Ross underground substation. This will be
19 provided early in the construction process to allow it to be used for construction.

20 **6.4.2 Standby and Emergency Power**

21 A 300kW emergency/standby diesel generator will be provided in the Central Utility Cavern to
22 serve standby and emergency loads. 48 hours of diesel fuel will be provided to operate the generator
23 when surface power is inoperable. This duration aligns with the stored LN for controlling argon
24 boil off, both of which were derived from historical power outages at the facility. Note that the
25 facility is fed by the local utility provider in a loop infrastructure, and therefore power to the site
26 has historically been very reliable – on the order of a few hours down per year. Within the facility,
27 power outages due to maintenance or unforeseen events are also at a very low rate. The following
28 4850L electrical loads are anticipated to be installed to the emergency/standby power system:

- 29 • Security

unless specific requirements that differ from this are provided by LBNF/SURF or the lab experiment design teams.

- 30 • IT System for communications
1 • Smoke control fans
2 • Mono rail
3 • Cryostat system controls

4 **6.4.3 Fire Alarm and Detection**

- 5 The 4850L will have notification devices installed to alarm the occupants of a fire. Notification
6 devices will consist of speakers and strobe lights. Manual pull stations will be provided within
7 200 ft of egress. Phones will be installed in the liquid argon chambers and every 400 ft along the
8 access drifts to communicate with the surface level command center.

9 An air sampling and gas detection system will be installed in the drifts and liquid argon detector
10 chamber as an early detection of a fire condition. The air sampling system will be connected into
11 the fire alarm system.

12 The fire alarm system will also interface with the oxygen deficiency hazard (ODH) system to
13 activate the fire alarm system and initiate an alarm at the respective level fire alarm panel and
14 at the surface level command center. Specific sounds and strobe colors will be identified based on
15 the type of alarm (fire, ODH, etc.).

16 **6.4.4 Lighting**

- 17 Suspended lights mounted at a height just below the lowest obstruction will be provided for all
18 drifts and ramps. Mounting is to be coordinated with conduit and supports of other systems
19 running overhead. Maintained average illumination of approximately 24 lux (2.4 foot candles) at
20 floor level will be provided throughout the drifts. Lighting control in drifts will be via low voltage
21 occupancy sensors and power packs suitable for high humidity environments.

22 **6.4.5 Grounding**

- 23 The grounding system will be designed to provide effective grounding to enable protective devices
24 to operate within a specified time during fault conditions, and to limit touch voltage under such
25 conditions. The grounding system will be designed for a maximum resistance of 5 ohms where
26 possible based on Mine Safety and Health Administration (MSHA) recommendations for ground
27 resistance in mines. Ground beds, consisting of an array of ground rods, will be installed at each
28 substation to provide low impedance to ground.

- 29 Electrical separation between the cryostat detectors and cavern utilities will be achieved by sepa-
1 rating the metal components (rebar, structure support, etc.) from each other. Inductors will be
2 installed between grounding systems to control noise between systems while also controlling touch
3 potential for safety.

4 **6.5 Plumbing**

- 5 Plumbing provided by CF, but specific to DUNE, includes plumbing for the cooling systems and
6 gas piping for nitrogen and argon delivery from the Cryogenics Compressor Building on surface to
7 the Central Utility Cavern. Beyond this the facility requires supplies of both potable and industrial
8 water, as well as a means to remove water inflows.

9 **6.5.1 Industrial Water**

- 10 An existing 4-inch industrial water riser will be used for construction and as a secondary fire
11 service. It is not feasible to run an uninterrupted main water supply line from grade level down
12 to serve the lower levels due to the extremely high hydrostatic pressure that would occur in the
13 system. A series of pressure reducing stations are located at regular intervals in intermediate levels
14 and at the 4850L in order to maintain the pressure within the capability of readily available piping.

15 **6.5.2 Potable Water**

- 16 Potable water is not required in large quantities for LBNF. The SURF experience has been that
17 plumbing potable water through the shafts for low volumes is not effective, as the pressure reducing
18 systems have the potential to introduce biological contaminants that result in the water no longer
19 meeting drinking water standards, especially in low flow situations. To address this, local filters
20 and ultraviolet treatment is done at the 4850L to make industrial water meet drinking water
21 standards. This system has been used successfully for several years at SURF.

22 **6.5.3 Chilled Water**

- 23 The DUNE equipment will produce a significant amount of heat which will be removed by LBNF-
24 provided chillers. Three chillers at 50% each have been selected to provide N+1 redundancy to
25 allow for maintenance. Heat from the chillers and various process loads will be rejected using a
26 spray chamber located at the east end of the 4850L LBNF caverns immediately before exhausting
27 into a new borehole providing a direct connection to the exhaust shaft to surface. The ventilation
28 air is a mixture of air from the Yates and Ross Shafts at approximately 68 degrees F. This volume
29 of air is such that the total heat rejected (2.9 MW or 822 Ton) will raise the air temperature to
30 no more than 95 degrees F.

31 6.5.4 Fire Suppression

- ire-supp
- 1 The source of fire water main will be the existing 4-inch industrial water main at Ross Shaft.
 - 2 The connection to this line will be at the 4100L, where a new sump with at least 27,000 gallons
 - 3 capacity will be built using sump walls in an existing drift to provide 90 minutes of capacity even
 - 4 if the supply were cut off. The fire protection system at the 4850L Campus will be a gravity fed
 - 5 system. There will be a connection to an existing 6-in industrial water main in the west drift fed
 - 6 from Yates Shaft, where a similar, but slightly larger at 50,000 gallons, sump has been built by
 - 7 SURF. This provides redundant supply from surface.

8 6.5.5 Drainage

- nd-drain
- 9 Drainage [17] from the drifts, mechanical electrical rooms (MERs), and any areas where spillage
 - 10 is likely to occur will be collected locally in sumps. Sumps will be located every 500 feet in any
 - 11 areas where drainage to the drifts is not practical. Sumps will be equipped with sump pumps in a
 - 12 staged configuration where each pump discharging to the adjacent sump until water is discharged
 - 13 to the #6 Winze, where it flows to the primary facility pool approximately 1,000 feet below the
 - 14 4850L. From there, the existing SURF dewatering system pumps the water in stages to the surface
 - 15 where it is treated before discharge into a nearby stream.

16 6.5.6 Sanitary Drainage

- an-drain
- 17 No sanitary drainage is included in the requirements for LBNF. Existing SURF facilities are
 - 18 planned to be used.

19 6.5.7 Nitrogen and Argon Gas Piping

- s-piping
- 20 Two 16-in and three 8-in mild steel pipes are provided by CF from the surface Cryogenics Com-
 - 21 pressor Building to the shaft, through the shaft, and across the 4850L to the Central Utility Cavern
 - 22 west entrance. The design and specifications of this piping are the responsibility of the Cryogen-
 - 23 ics Infrastructure Project team. The supply and installation within the Cryogenics Compressor
 - 24 Building and the central Utility Cavern is also the responsibility of the Cryogenics Infrastructure
 - 25 Project.

26 6.6 Cyberinfrastructure

- nd-cyber
- 27 The Structured Cable System design will be based on uniform cable distribution with a star
 - 28 topology. New fiber connections will be extended to the 4850 level from the Ross Dry Building,

and will be dedicated to the use of LBNF experiments at the 4850 level. The design provides one (1) 96-strand single mode armored fiber optic cable from the DUNE Control room dedicated to the experiments. A second 96 stand single mode armored fiber optic cable will be routed through the Yates shaft to provide redundancy for data systems. Figure 6.3 shows the fiber distribution network for LBNF.




Figure 6.3: Fiber distribution system for LBNF (Arup)

Voice communications are provided via two-way radios and phones distributed throughout the underground spaces (in every room as well as every 500 ft in drifts). Two-way radios and cellular phones utilize a leaky feeder system to ensure communications over long distance without line of site. These leaky feeders are cables that act as antennas installed the length of all drifts and shafts. Standard phones utilize Voice over Internet Protocol (VoIP) to provide communication though the fiber optic data backbone.

The data system is designed to provide 10-Gigabit Ethernet in the backbone and 1-Gigabit Ether-net to connected systems (computers). This system is intentionally left at a lesser level of design due to the continuous progression and advancement of technology that will almost certainly result in more advanced technologies than are currently available being utilized at the time of construction.

¹⁶ 6.7 Waste Rock Handling

- ¹ Prior to the commencement of any excavation activities, it will be necessary to establish a waste rock handling system

³ Josh says: Need to determine whether this terminology is acceptable from Pepin

- ⁴ . The capacity of this system will be equivalent to what was in place during mining. There are a number of components to the waste rock handling system, including refurbishing the Ross Shaft hoisting system, the Ross Shaft crushers, and a new conveying system to transport rock downhill to the Kirk Road, as seen in Figure 6.4.




Figure 6.4: Waste rock handling system route (SRK, Courtesy SURF)

- ⁸ The systems utilize experience and equipment from the former Homestake Mining Company legacy, where rock was removed to the surface using skips in both the Yates and Ross Shafts. At the headframe of each shaft, the material was crushed to a nominal 3/4 in, passed through ore bins, and was transported via underground rail to the mill system. All systems from the underground to the crushers will be rehabilitated from the original systems, though the material may not be required to be crushed as fine as it was historically, and therefore some components of the system may not be re-used.

¹⁵ References

- [1] LBNF/DUNE, “LBNF/DUNE Conceptual Design Report (CDR),” tech. rep., 2015. DUNE Doc 180-183.
- [2] Particle Physics Project Prioritization Panel, “Building for Discovery; Strategic Plan for U.S. Particle Physics in the Global Context,” 2014. http://science.energy.gov/~/media/hep/hepap/pdf/May%202014/FINAL_P5_Report_Interactive_060214.pdf.
- [3] CERN Council, “The European Strategy for Particle Physics, Update 2013,” 2013. <http://council.web.cern.ch/council/en/EuropeanStrategy/ESParticlePhysics.html>.
- [4] LBNF/DUNE, “LBNF/DUNE Science Requirements,” tech. rep., 2015. DUNE Doc 112.
- [5] Arup, “LBNF FSCF 100% Preliminary Design Report ,” tech. rep., 2015. DUNE Doc 136.
- [6] LBNF, “LBNF Draft Comprehensive Logistics Report,” tech. rep., 2015. DUNE Doc 423.